Extraordinary

Federal Republic of Nigeria Official Gazette

No. 122 **Lagos - 7th July, 2023** **Vol. 110**

Government Notice No. 95

The following is published as supplement to this *Gazette* :

S.I. No.	*Short Title*		*Page*
51	Persons with Disabilities (Accessibility) Regulations, 2023	..	B1343-1513

Printed and Published by The Federal Government Printer, Lagos, Nigeria
FGP 110/52023/150

Annual Subscription from 1st January, 2023 is Local : ₦50,000.00 Overseas : N 65,000.00 [Surface Mail] N 80,000.00 [Second Class Air Mail]. Present issue ₦3,500 per copy. Subscribers who wish to obtain *Gazette* after 1st January should apply to the Federal Government Printer, Lagos for amended Subscriptions.

B 1342

DISCRIMINATION AGAINST PERSONS WITH DISABILITIES (PROHIBITION) ACT, NO 2, 2018

PERSONS WITH DISABILITIES (ACCESSIBILITY) REGULATIONS, 2023

ARRANGEMENT OF REGULATIONS

Regulation :

CHAPTER ONE—OBJECTIVES AND APPLICATION

1. Objectives
2. Application

CHAPTER TWO—EXTERIOR OR OUTDOOR AREAS

PART I—EXTERIOR ROUTES

3. Bridges with pedestrian access
4. Zebra crossing or crosswalks
5. Kerb ramps or kerb cuts on public right of way
6. Grades and elevation changes
7. Guards and handrails (general)
8. Vertical clearance
9. Lay-bys for vehicles (Passenger loading zones)
10. Paths, sidewalks and walkways
11. Pedestrian route
12. Ramps
13. Ramps with mounted handrails
14. Tactile marking
15. Stairs and steps
16. Handrails on stairs
17. Traffic islands (median) on public right of way
18. Drainage gratings

PART II—TRANSPORT INFRASTRUCTURE

19. Accessible routes to entrances
20. Bus or public transit shelters
21. Bus stops
22. Rail Platforms
23. Emergency routes
24. Parking
25. Garages and enclosed parking spaces
26. Clear space or ground space around facilities
27. Road Drainage
28. Signage (general)

PART III—ENTERTAINMENT AND RECREATIONAL FACILITIES

29. Access to entertainment and recreational facilities
30. Sports fields and spectator areas
31. Amphitheatres
32. Grandstands and viewing areas
33. Outdoor eating and entertainment spaces, balconies and terraces
34. Boardwalks
35. Campgrounds
36. Community mailboxes
37. Recreational Facilities
38. Amusement rides
39. Recreational Boating Facilities
40. Docks
41. Swimming pools and wading pools
42. Sloped entries to a swimming or wading pool
43. Transfer platform in a pool
44. Play grounds
45. Terraces and patios of a public building
46. Path and footbridges
47. Open Viewing location and instrument
48. Waterfront areas
49. Wildlife reserves and conservation areas
50. Market places
51. Walkways and aisles
52. Vending tables
53. Fire safety
54. Access to seating area

PART IV—OUTDOOR AMENITIES

55. Access to outdoor amenities
56. Benches and seats
57. Bicycle and motorcycle racks
58. Drinking fountains
59. Accessible restrooms
60. Toilet
61. Washbasins
62. Accessible washrooms
63. Shower compartment
64. Bath compartment
65. Public telephones

PART V—OUTDOOR SUPPORT SYSTEMS

66. Zebra crossing and pedestrian signals
67. Lighting for exterior areas not including roads
68. Public address systems
69. Way-finding
70. Traffic signals

PART VI—OTHER EXTERIOR FEATURES

71. Visual and tactile cues
72. Colour, pattern and texture
73. Construction site
74. Freestanding objects
75. Waste handling infrastructure
76. Gates and openings
77. Landscape materials and planting
78. Materials and finishes
79. Maintenance of outdoor features
80. Safety and security

CHAPTER THREE—REQUIREMENTS FOR INTERIOR OR INDOOR AREAS

PART I—ACCESS TO THE BUILDING

81. Pathway from a parking space to the building
82. Canopies and weather protection
83. Entrance
84. Reception area or information desk
85. Doors and doorways
86. Self-closing swing doors
87. Power-operated or automated doors
88. Double-leaf doors and gates
89. Doorways without doors
90. Recessed doors or gates
91. Door and gate hardware, locks and closers
92. Manual door opening and closing devices
93. Controlled door opening and closing devices
94. Hinges
95. Locks and latches
96. Door bolts
97. Glazed screens and sidelights
98. Cupboard door hardware
99. Mats and mat sinkages
100. Thresholds
101. Vestibules
102. Waiting areas
103. Seating layouts

PART II—INTERIOR ROUTES

104. Interior circulation routes
105. Aisles and passageways
106. Projections into aisles and passageways
107. Doors across passageways
108. Fire escape routes via horizontal circulation
109. Lifts
110. Passenger lift
111. Platform lifts

112. Interior ramps
113. Lighting platforms or daises
114. Safe holding areas
115. Stairs and steps
116. Turnstiles and control gates

PART III—INTERIOR AMENITIES

117. Access to interior amenities
118. Hanging racks
119. Drinking fountains
120. Equipment and furniture
121. Storage facilities
122. Access to storage facilities
123. Mailboxes
124. Mirrors
125. Restrooms and washrooms
126. Work surface layout in a work station
127. Work surface accessories
128. Vending machines
129. Windows and window hardware

PART IV—INTERIOR SYSTEMS AND CONTROLS

130. Acoustic attenuating features
131. Audible and visual information
132. Communication systems
132. Braille
134. Symbols of accessibility
135. Controls and electrical installations
136. Electrical power supply
137. Fire emergency systems and signals
138. HVAC and cooling systems
139. Information systems and directories
140. Artificial lighting
141. Natural lighting
142. Listening devices
143. Assistive listening systems
144. Public address systems
145. Telephones
146. Signage and way-finding

PART V—SPECIAL FACILITIES AND AREAS

147. Automated Teller Machines (ATMs)
148. Ticketing machines
149. Video and image display terminals
150. Restaurants and other eateries
151. Place of Worship
152. Public institutions in the criminal justice system
153. Health Care and social welfare facilities

154. Libraries
155. Schools and Education Centres
156. Public residence
157. Kitchen in a public residence
158. Special washroom in a public residence
159. Bedroom in a public residence
160. Shops and shopping malls
161. Accessible cabin coach

PART VI—OTHER INTERIOR FEATURES

162. Life safety plan
163. Maintenance

CHAPTER FOUR—ENFORCEMENT AND COMPLIANCE

164. Inter-agency collaboration
165. Compliance procedures
166. National Disability Compliance Certificate
167. Capacity building on accessibility and compliance
168. Administrative penalty
169. Powers to seal off building

CHAPTER FIVE—MISCELLANEOUS PROVISIONS

170. Issuance of guidelines
171. Interpretation
172. Citation

SCHEDULES

B 1348

S. I. No. 51 of 2023

DISCRIMINATION AGAINST PERSONS WITH DISABILITIES (PROHIBITION) ACT, NO 2, 2018

PERSONS WITH DISABILITIES (ACCESSIBILITY) REGULATIONS, 2023

[22*nd day of May*, 2023] Commencement.

In exercise of the powers conferred on it by section 56 of the Discrimination Against Persons with Disabilities (Prohibition) Act, 2018 ("the Act") and all other powers enabling it in that behalf, the Governing Council of the National Commission for Persons with Disabilities ("the Commission"), makes the following Regulations —

CHAPTER ONE

OBJECTIVES AND APPLICATION

Objectives.

1. The objectives of these Regulations are to—

(a) ensure effective collaboration with relevant agencies towards ensuring ensuring easy and unimpeded access to services in the Nigerian built environment by persons with disabilities ;

(b) provide specifications for policy makers, regulators, implementers, and service providers to ensure quality and non-discriminatory services in the Nigerian built environment ;

(c) provide standards and codes for the design and construction of an accessible built environment, including roads, and transportation facilities ;

(d) provide a tool for measuring or auditing universal accessibility in the built environment ;

(e) guide developers, designers and other persons involved in the built environment process in incorporating accessibility principles in the planning, design, and execution stages of building work ; and

(*f*) increase awareness on accessibility standards and the need for a barrier-free design in the built environment.

Application.

2. These Regulations shall apply to—

(a) Ministries, Departments, and Agencies of Government (MDAs) ;

(b) international organisations, and non-governmental organisations ;

(c) structures and facilities accessible to members of the public, and their owners ; and

(d) persons undertaking any activity in relation to built environment, including audit teams, facility managers, public officials, architects, engineers, and developers.

CHAPTER TWO—EXTERIOR OR OUTDOOR AREAS

PART I—EXTERIOR ROUTES

Bridges with pedestrian access.

3.—(1) A person involved in built environment shall ensure that pedestrian routes are—

(a) safe and easy to use by persons with disabilities ; and

(b) easily identifiable, clearly separated from vehicular routes, and free of obstacles at all times.

(2) In the case of a bridge with pedestrian access—

(a) pedestrian sidewalks located on either side of the bridges shall have—

(i) a slope not greater than 1 : 20 to the ground level, and

(ii) where practicable, a cross slope not greater than 1 : 50 to the ground level ;

(b) sidewalk on the bridge shall be a minimum width of –

(i) 1220 mm, where minimal pedestrian traffic is expected, or

(ii) 1800mm, where a high pedestrian traffic is expected ;

(c) handrails or guards located beside sidewalks shall be –

(i) easy to grasp,

(ii) a maximum width of 50mm, and

(iii) mounted at a suitable height,

as specified in Figure 1.008 of the First Schedule to these Regulations ; and

(d) pedestrian footbridges shall, where practicable, have ramp options rather than stairways only.

Zebra crossing or crosswalks.

4.—(1) A zebra crossing or crosswalk at a roadway intersection shall—

(a) be located —

(i) to ensure that the sidewalk and the zebra crossing or crosswalk are at right angles to one another,

(ii) to ensure a clear view of traffic in each direction, and

(iii) at sufficient distance of 20,000 mm from the intersection to permit a safe crossing ;

(b) include appropriate kerb ramps at each end ; and

(c) be free of obstacles, such as light stands, traffic signal supports, boxes, or waste containers.

(2) A zebra crossing or crosswalk shall —

(a) have kerb ramps at the end of a walkway, where sidewalks are provided, or where level differences exceeding 19mm occur, as specified in Figure 1.001 of the First Schedule to these Regulations ;

(b) be of a minimum width of 3,000mm, and clearly marked by 100 mm, painted white lines or by using distinctive, highly contrasting paving materials ; and

(c) have tactile paving.

(3) An intermediate traffic island shall —

(a) include kerb ramps ;

(b) be leveled to street paving ; and

(c) be clearly marked by white lines or distinctive highly contrasting paving.

(4) Where a traffic light or pedestrian crossover is provided at zebra crossing or crosswalk —

(a) a clearly identifiable pedestrian pushbutton shall be located adjacent to the zebra crossing or crosswalk and mounted on a nearby post at a height of 1065mm ; and

(b) paving shall be level at posts, providing a minimum of 915mm x 1220mm clear approach area for pedestrians,

as specified in Figure 1.002 of the First Schedule to these Regulations.

Kerb ramps or kerb cuts on public right of way.

5.—(1) A kerb ramp shall be provided, where there is a level difference between a sidewalk or pedestrian pathway and the road surface, including where a pedestrian zebra crossing or crosswalk is provided, as specified in Figure 1.003 of the First Schedule to these Regulations.

(2) A kerb ramp transition slope shall be of a minimum length of 1500mm, as specified in Figure 1.004 of the First Schedule to these Regulations.

(3) The minimum width of the kerb ramp shall be 900mm between two flared sides of a minimum width of 1200mm.

(4) A kerb ramp shall —

(a) have a minimum slope at a ratio of 1 :20 for a short kerb, and a maximum slope of the flare at 1 : 10 ; and

(b) be made of non-slippery materials, with contrasted colours.

(5) A kerb ramp or kerb cut shall have tactile markings, and be provided on both sides of a zebra or pedestrian crossing, particularly where catch basin is necessary.

(6) A kerb ramp shall —

(a) have a minimum width of 1500mm, where the ramp is located on a public thoroughfare, as specified in Figure 1.003 of the First Schedule to these Regulations ;

(b) have flared, non-slip sides, and be clearly different from the surrounding sidewalk and at right angles to the path of travel, as specified See Figure 1.005 of the First Schedule to these Regulations ;

(c) have at its lower edge, a cane detectable rounded edge of 13mm in height ;

(d) have at its top, a level landing with a minimum depth of 1065mm, as specified in Figure 1.004 of the First Schedule to these Regulations ;

(e) be of a different textured material, as specified in Figure 1.005 of the First Schedule to these Regulations ; and

(*f*) be free from accumulated rainwater, and contain no manhole, storm gratings, or other obstacles.

Grades and elevation changes.

6.—(1) A grade on a road and sidewalk shall be designed and constructed to ensure that the slope of pedestrian route does not exceed 1:20.

(2) An accessible path of travel shall have kerb cuts to keep the sidewalk as level as possible.

(3) A ramp shall be provided, where an elevation change exceeding 1:20 is necessary, or where steps are unavoidable.

(4) Where a sloped landscaped area exceeding 3:1 is located adjacent to a pedestrian route, a clear boundary edge, such as an up-stand kerb or retaining wall with a minimum height of 150mm shall be provided, as specified in Figures 1.06 and 1.007 of the First Schedule to these Regulations.

(5) Where a grade drop-off adjacent to the sidewalk is 460mm or more, a handrail or guard shall be provided, as specified in Figure 1.007 of the First Schedule to these Regulations.

Guards and handrails (general).

7.—(1) There shall be continuous handrails on both sides of a ramp or stairs, including where three or more staircases are provided.

(2) A handrail shall —

(a) be easy to grip ;

(b) be made preferably of metal or any other approved strong and sturdy material ;

(c) not be too smooth or having spikes or sharp edges ;

(d) not exceed 50mm in diameter ; and

(e) be mounted between 865mm and 965mm, above stair nosing,

as specified in Figures 1.008 and 1.009 First Schedule to these Regulations.

(3) The distance between a handrail and a vertical wall surface shall be a minimum width of 40mm, and handrails shall continue unbroken along the stairs and on the landing area.

(4) A level section of the handrail shall extend to minimum length of 300mm beyond the top and bottom risers of a flight of stairs or ramps, as specified in Figure 1.010 of the First Schedule to these Regulations.

(5) A handrail on the inside curve of stairs or ramps shall not extend beyond 100mm.

(6) The end of a handrail shall terminate by turning down or by going into the wall.

(7) A guard shall be put in place on both sides of a ramp, where height difference is sizable.

(8) A guard or handrail provided on a terrace or viewing platform shall be designed to ensure that a seated person can see under the handrail or guard.

(9) A guard or handrail shall not be located within 1000mm of a roadway.

(10) A handrail shall measure at a height of —

(a) 600mm — 700mm from the ground level for use of by children and wheelchair users ; and

(b) 800mm — 900mm for use by other users.

(11) In order to prevent wheels from falling out of the ramp edge, rails for the wheels shall be placed at a height of 150mm-200mm, at the bottom of the railing.

(12) Where the width of a ramp exceeds a width off 3,000mm, handrails located along the ramp shall be painted in contrasting colours and where stairs exceed 2,700mm, an intermediate handrail with a minimum width of 1500mm shall be provided on one side of the stairs.

Vertical clearance.

8.—(1) A minimum vertical clearance of 2030mm shall be allowed, for external and internal walkways.

(2) Where vertical clearance is less than 2030mm, a guardrail or other barriers shall be provided.

(3) The leading edge of a guardrail or barrier provided pursuant to sub-regulation (2) of this regulation shall be positioned at least 685mm above the finished floor or ground, as specified in Figure 1.012 in the First Schedule to these Regulations.

(4) Paving surfaces at the top and bottom of a flights of stairs or steps shall include a cane detectable and textured walking surface measuring a minimum width of 915mm, forward of the first riser, and continuous from the top of the stair, as an early warning of an impending level change to persons with visual disabilities, as specified in Figure 1.025 of the First Schedule to these Regulations.

(5) Exterior doors that open onto landings shall be avoided, where possible, in order to minimize hazards, and where such doors are unavoidable, the landing width shall be increased to 1670mm, provided that no door shall open onto any sloping section of a ramp.

Lay-bys for vehicles (Passenger loading zones).

9.—(1) A special lay-by area, free of other vehicular traffic shall be provided at bus stops, train stations and other similar places, as specified in Figure 1.013 in the First Schedule to these Regulations.

(2) A lay-by space shall —

(a) be located within 30000mm of a main or other accessible entrance ;

(b) be leveled with a minimum width of 3050mm and length of 7925mm, and

(c) have a kerb cut located towards the rear of the space.

(3) A lay-by shall have headroom with a minimum clearance of 3555mm for special transit vehicles and adapted vans, as specified in Figure 1.013 in the First Schedule to these Regulations.

(4) A sidewalk adjacent to lay-by headroom shall have a minimum clearance of 1980mm width, to accommodate side-loading vehicles with hydraulic lifts or cranes.

(5) Where a shelter is provided at a bus stop—

(a) the bus stop pad may be located within or outside of the shelter ; and

(b) the shelter shall —

(i) have a clear floor or ground space measuring a minimum length of 2,440mm and minimum width of 1525mm, and

(ii) be connected by an accessible route to a boarding and alighting area.

(6) A bus stop boarding and alighting area shall have a—

(a) firm and stable surface ; and

(b) clear minimum length of 2440mm, measured perpendicular to the curb or vehicle roadway edge, and a clear minimum width of 1525mm, measured parallel to the vehicle roadway.

(7) A vehicle boarding and alighting area shall be connected to a street, sidewalk, or walkway by an accessible route.

(8) The slope of a bus stop boarding and alighting area—

(a) parallel to the roadway, shall be the same as the roadway, to the maximum extent practicable ; and

(b) perpendicular to the roadway, shall not be steeper than 1:48.

(9) Kerb ramps shall be provided at passenger pick-up points, where the difference in road pavement and sidewalk levels are greater than 19mm.

(10) Van parking spaces at passenger pick-up points shall be a minimum of 7315mm in length by 2590mm in width, as specified in Figure 1.032 of the First Schedule to these Regulations.

(11) A designated passenger pick-up point shall have a sidewalk or safe pedestrian zone, located behind the vehicle and at the passenger boarding side of the vehicle, a minimum of 2000mm wide in length or width of the boarding space, to ensure safe loading or boarding and unloading or alighting.

(12) A designated passenger pick-up point shall be marked with an internationally recognized symbol of accessibility.

Paths, sidewalks and walkways.

10.—(1) An entrance path or sidewalk in a public right of way or walkways shall be made of firm, level, and non-slip materials, and of a minimum width of 1800mm such as to allow atleast two wheelchairs pass one another, where two-way traffic is expected.

(2) A sidewalk shall not exceed a maximum gradient of 1:20, where it exceeds the maximum gradient, it shall be considered a ramp of which handrails shall be installed, except where it is prevented by site conditions, as specified in Figure 1.027 in the First Schedule to these Regulations.

(3) A walkway or path around a residential environment shall be a minimum of 1100mm, and widened to a width of 1675mm at 30000mm intervals to accommodate persons using mobility aids.

(4) Unit paving materials used in sidewalks, paths and walkways shall have joints with a maximum width of 6mm, as specified in Figure 1.016 and 1.025 in the First Schedule to these Regulations.

(5) Where grating is to be located on sidewalks, opening in the grating shall be of a maximum width of 13mm, and bars of grating shall be perpendicular to

the path of travel, as specified in Figure 1.017 in the First Schedule to these Regulations.

(6) Clearly marked continuous amenity strips shall be used at the edge of a sidewalk to accommodate freestanding objects and other amenities.

(7) The strips referred to in sub-regulation (6) of this regulation shall —

(a) be of a minimum width of 610mm ; and

(b) separated from a pedestrian walkway by a contrasting colour ; and

(c) cane detectable border that is a minimum width of 305mm, as specified in Figure 1.006 in the First Schedule to these Regulations.

Pedestrian route.

11. —(1) A pedestrian route shall be a minimum width of 1500mm.

(2) A pedestrian route shall be free of protruding obstacles, overhanging signs, or any other obstacle in the walking area, as specified in Figures 1.006, 1.07 and 1.018 of the First Schedule to these Regulations.

(3) The maximum allowable protrusion of objects into a pedestrian route shall be 100mm from grade to a height of 685mm from the floor.

Ramps.

12.—(1) A ramp shall be provided, where gradient is more than 1:20.

(2) A ramp provided under sub-regulation (1) of this regulation shall comply with the criteria specified in regulation 6 of these Regulations.

Ramps with mounted handrails.

13.—(1) Ramp with mounted handrail shall be of a maximum width of 1100mm, and a minimum of 1015mm between handrails.

(2) For intermediate level landings, a minimum depth of 1670mm by the same width of the ramp shall be provided, and level landings at the top and bottom of the ramp shall be a minimum of 1670mm by 1670mm, as specified in Figures 1.021and 1.024 of the First Schedule to these Regulations.

(3) Where a ramp returns upon itself, or a door opens out onto a ramp, the level platform area shall measure a minimum length of 1,670mm and minimum width of 1,670mm, and an additional distance of 600mm for a door opening onto the landing, as specified in Figures 1.022 and 1.023 of the First Schedule to these Regulations.

(4) A ramp with slope between 1:20 and 1:12 shall have handrails on both sides, provided that a ramp with a gradient higher than 1:12 shall not be erected in a public building.

Tactile marking.

14. A tactile marking of 900mm width with contrasted colours shall be placed at the beginning and end of the ramp, which serve to alert a person with visual disability about the length and width of the ramp.

Stairs and steps.

15.—(1) Steps or stairs shall —

(a) have uniform closed vertical risers with a height between 100mm and 180mm ;

(b) not have open risers ;

(c) have uniform horizontal treads with depth between 280mm and 425mm ;

(d) have handrails as specified in regulation 16 of these Regulations ; and

(e) be at least 1200mm wide.

(2) Stairs or steps with nosing at the edge of each tread shall be a maximum length of 25mm.

(3) The edges of a step or stair shall be of a contrasting colour, and be made from anti-slip material.

(4) The landing at the top and bottom of the stairs shall —

(a) measure a minimum length of 1200mm and a minimum width of 1200mm ; and

(b) be clear of any door swings or other obstructions.

(5) Tactile warning blocks shall be installed at the landing of each flight of stairs, top and bottom.

Handrails on stairs.

16.—(1) Where stairs exceed a width of 3000mm, a handrail shall be installed in the centre.

(2) Where stairs having vertical clearance has space underneath, it shall comply with the provisions of regulation 8 of these Regulations.

(3) Outdoor steps shall be of a firm, non-slip material with a recommended maximum rise of 180mm and a maximum tread length of 300mm, as specified in Figure 1.047 of the First Schedule to these Regulations.

(4) The provisions of regulation 7 of these Regulations shall apply to this regulation.

(5) Tread nosing shall be clearly marked with either a brightly painted non-slip finish or include an integrated non-slip nosing that clearly contrasts in tone or colour from the tread.

(6) Continuous handrails shall be provided on both sides of outdoor flights of stairs or steps, including where three or more steps staircases are provided.

(7) Where a flight of stairs or steps is of a width of 2200mm or more, an intermediate handrail shall be installed.

Traffic islands (median) on public right of way.

17.—(1) A traffic island shall be built of materials and finishes that are easily distinguishable from the surrounding paving.

(2) A pedestrian zebra crossing or crosswalk that crosses a traffic island shall be level with the main crossing or have kerb ramps for persons using mobility aids.

(3) A traffic island shall be of a minimum width of 1500mm, as specified in Figure 1.026 of the First Schedule to these Regulations.

(4) Where the crossing surface at a traffic island is level with the paving, the safe waiting area of the traffic island shall be made clearly identifiable by using different materials, contrasting colours, or textures that are detectable by persons with visual disability.

Drainage gratings.

18.—(1) Drainage gratings shall be positioned beyond the boundaries of the access route.

(2) Where gratings are necessary along an access-route, they shall be set to flush with the surrounding surface.

(3) Slots in gratings shall be of a maximum width of 13mm, and set at right angles to the dominant line of travel.

(4) The diameter of circular holes in gratings shall not exceed 18mm.

(5) Dished channels shall not be incorporated within an access route.

PART II—TRANSPORT INFRASTRUCTURE

Accessible routes to entrances.

19.—(1) A pedestrian route to a main entrance or other accessible entrance to a building and other components of public transportation systems, including buses, taxis, ambulances and trains shall be designed to provide a safe, direct, level and obstacle-free path of travel.

(2) Accessible route of a minimum width of 1200mm, and made from a firm nonslip material shall be provided at the site boundary to the main entrance or other accessible entrance.

(3) Accessible pedestrian routes to an entrance shall not be designed to cross into a vehicular route.

(4) Where an accessible pedestrian route crosses into a vehicular route, crossings with kerb ramps marked with a bright contrasting colour or white lines, or a distinct paving shall be provided.

(5) A slope on a walkway shall not exceed 1 :20, provided that where steeper walks are necessary, nearby stairs shall be provided and the slopes shall be treated as ramps, as specified in Figure 1.027 of the First Schedule to these Regulations.

(6) Where the length of an accessible route to accessible entrance exceeds 30000mm, a rest area may, where practicable, be provided at intervals of 30000mm.

(7) A rest area of a minimum width of 1200mm fitted with or having space for furniture shall be located to one side of the walkway.

Bus or public transit shelters.

20.—(1) A bus or public transit shelter shall be —

(a) located on a firm and level base of 4265mm x 1830mm ; and

(b) at the same elevation as the sidewalk or walkway.

(2) Clearances around a shelter, including clearance on the side of a landing pad, shall measure a minimum width of 1100mm to allow for easy access by pedestrians as specified in Figure 1.028 of the First Schedule to these Regulations.

(3) A bus or public transit shelter shall be designed to provide a clear view of on-coming traffic, and have a minimum interior length of 2185mm to accommodate persons using mobility aids.

(4) A bus or public transit shelter shall have —

(a) a minimum of one seat measuring between 405mm and 460mm high ;

(b) a resting ledge, or handrail mounted at a height of 760mm to 815mm ;

(c) provide a minimum clear floor or ground space entirely within the shelter in compliance with these Regulations ; and

(d) be connected by an accessible route to a boarding and alighting area in compliance with these Regulations.

(5) A glazed panel forming part of a bus shelter shall have 50mm diameter stickers or a continuous coloured line, mounted at a maximum height of 1500mm from centre to centre apart.

Bus stops.

21.—(1) A waiting area at bus stop shall be —

(a) constructed using firm materials ;

(b) on a level of minimum of 2000mm width by 12000mm length ; and

(c) incorporate seating or a shelter.

(2) A bus stop area shall be free from hawking and freestanding objects.

(3) The boarding point of a bus stop shall be sizeably spacious to—

(a) facilitate disembarkation from the centre door of a bus ;

(b) provide for buses to stand at the stop ; and

(c) provide additional standing space for intending passengers.

(4) Pursuant to sub-regulation (1) of this regulation, where an adjacent footpath is not wide enough to provide an access path between boarding or disembarkation points, a bus stop shall incorporate an access path measuring a minimum width of 1200mm, as specified in Figure 1.029 of the First Schedule to these Regulations.

Rail Platforms.

22.—(1) A boarding and alighting area shall be connected to a street, sidewalk, or pedestrian paths by an accessible route.

(2) A rail platform —

(a) shall not exceed a slope of 1 :48 in all directions,

(b) have firm non-slippery surface ; and

(c) be of the same level to the door of the train.

(3) Notwithstanding the provisions of sub-regulation (2)(*c*) of this regulation, where a platform is not of the same level to the door of the train, a zigzag lift or a transfer platform shall be provided for the use of persons with physical disabilities.

(4) Where a rail platform serves coaches operating on existing track or track laid in existing roadway, the slope of the platform parallel to the track shall be permitted to be equal to the slope of the roadway or existing track.

(5) A platform boarding edges that is not protected by a platform screen or guard shall have detectable warnings along the full length of the platform.

(6) A coach that is boarded from a sidewalk or street-level shall have a low-level platform measured at a minimum height of 205 mm.

Emergency routes.

23. Vehicular routes, used by emergency vehicles, including fire trucks and ambulances, shall be clearly identified by a relevant signage, and not cross nor intersect with a primary pedestrian route to a main entrance or other accessible entrance.

Parking.

24.—(1) The surface of a car park shall be flat, firm, and non-slippery.

(2) A parking space reserved for persons with disabilities shall be provided within 30,000mm to the entrance of the building, and measure a minimum of 2,500mm x 5,000mm.

(3) An access area measuring a width of 1,200mm and clearly marked with contrasted colours shall be reserved on the side and at the rear of designated parking spaces, as specified in figure 1.029, 1.030, 1.031 and 1.032 of the First Schedule to these Regulations.

(4) Where the location for reserved parking space is not close to the building entrance, a covered footway or seats shall be provided at intervals along the accessible route.

(5) A vertical sign indicating an accessible parking space reserved for persons with disabilities shall be positioned at a height of 2000mm.

(6) An internationally recognized symbol of accessibility shall be painted on the ground within the accessible parking spaces.

(7) Where payment is required for parking, an audio function enabled ticket vending machine shall, be provided.

(8) For every 100 accessible parking spaces, a minimum of 8 spaces shall be reserved for persons with disabilities, provided that, where the number of parking spaces is less than 25, a minimum of two accessible parking spaces shall be provided.

(9) For every 100 accessible parking spaces, a minimum of one space measuring a minimum of 3660mm wide and 5385mm long, shall be reserved for a wheelchair van, as specified in Figure 1.032 of the First Schedule to these Regulations.

(10) Where space permits, at least one large designated parking space of 4800mm wide x 8000mm long, shall be provided to cater for commercial vehicles converted for side or rear access using hoists or ramps.

(11) A headroom clearance for van parking spaces shall be a minimum height of 2750mm.

(12) Walkway from a reserved parking to an accessible entrance into a building shall be a minimum width of 1200mm, firm, level, made of non-slip material, and have a texture contrasted with the adjacent surfaces.

(13) Where covered or underground parking space is provided, access and exit routes, including ramps serving such spaces, shall have a clear headroom of 2285mm below beams, pipes, or sprinkler heads.

(14) A suitable kerb ramp from the accessible car parking area shall be provided where the elevation differential is greater than 13mm.

(15) A parking lot and an access route from a lot to a building entrance shall be equipped with artificial lighting measuring 20 lumens per square-meter, and 100 lumens per square-meter on ramps or steps.

Garages and enclosed parking spaces.

25.—(1) A garage or enclosed parking space in a public build environment shall —

(a) be leveled, and be on the same level as the entrance to a building or the main access route to and from the car park ;

(b) permit the use of a wheelchair hoist ; and

(c) have a vertical clearance of a minimum height of 2600mm.

(2) Without prejudice to sub-regulation (1) of this regulation, where it is not practicable to have a reserved parking space on the same level as an entrance into a building or main access route, a passenger lift or ramp shall be provided to link the different levels of the car park.

(3) Where a power-operated door is fitted at the entrance of a garage or enclosed parking space, it shall be capable of being operated from inside a vehicle.

(4) The dimensions of a garage or enclosed parking space reserved for a wheelchair user shall be as specified in Figure 1.032 of the First Schedule to these Regulations.

Clear space or ground space around facilities.

26.—(1) Clear floor or ground space shall be a minimum length of 760mm and a minimum width of 1220mm.

(2) Unless otherwise specified, clear floor or ground space shall be —

(a) permitted to include knee and toe clearance for a wheelchair user ; and

(b) positioned for either forward or parallel approach to an element,

as specified in Figure 1.034 of the First Schedule to these Regulations.

(3) A full unobstructed side of the clear floor or ground space shall adjoin an accessible route or adjoin another clear floor or ground space.

(4) Where a clear floor or ground space is located in an alcove or otherwise confined on all or part of three sides, additional maneuvering clearance shall be provided as specified in Figures 1.034 and 1.035 of the First Schedule to these Regulations.

(5) An alcove shall have a —

(a) minimum width of 915mm, where its receded depth exceeds 610mm ; or

(b) minimum width of 1525mm where its receded depth exceeds 380mm.

Road Drainage

27. Road drainage shall be as specified in regulation 18 of these Regulations.

Signage (general)

28.—(1) A signage shall be—

(a) readable, legible and, where practicable, audible ;

(b) illuminated and easy to locate ; and

(c) made of robust materials that are easy to change, clean and repair.

(2) A visual sign shall be placed at a maximum height of 1900mm from the ground level.

(3) Information expressed in a text format shall be supplemented with standard graphical symbols to facilitate comprehension.

(4) Pedestrian signage shall be provided in relief and braille options.

(5) Signages shall not be placed —

(a) within close proximity ; and

(b) in the case of visual material, too close to wall fixed signs.

(6) In the case of a market, signage shall be erected at the entrance of a market and within the concourse of stalls to provide information and direction.

(7) Audio-visual systems for information shall be installed on signages.

PART III—ENTERTAINMENT AND RECREATIONAL FACILITIES

Access to entertainment and recreational facilities.

29.—(1) Accessible seating shall be provided for wheelchair users in accordance with Table 1.3 of the First Schedule to these Regulations.

(2) Accessible seating shall be —

(a) suitable to accommodate a person sitting beside a wheelchair user ;

(b) provided in a range of vantage points within a building, where a seat is provided for non-disabled members of an audience.

(3) A space adjacent to some seats shall be provided, to accomodate an assistance dog to rest away from the main circulation route.

(4) Fire safety arrangements, including means of escape, shall comply with the relevant provisions prescribed under these Regulations.

Sports fields and spectator areas.

30.—(1) Public sports fields, parking areas, entrances and spectator areas shall be accessible to persons with disabilities.

(2) Controlled access points, including turnstiles, shall be designed to accommodate the free movement of mobility aids through an adjacent gate a minimum width of 915mm.

(3) Level and accessible seating areas shall be provided beside sports fields for spectators and athletes with disabilities.

(4) Public viewing areas shall be in accordance with the provisions on viewing areas, as specified under these Regulations.

(5) Public toilets, urinals, bathrooms, and changing rooms shall be in accordance with provisions prescribed for outdoor amenities under these Regulations.

Amphitheatres.

31.—(1) Exterior amphitheatres or performance arenas shall include seating areas made accessible to persons using mobility aids, with at least two spaces provided side by side, and a minimum of 3 *percent* of all spaces shall be reserved for persons using mobility aids.

(2) Fixed or portable seating in an amphitheatre for persons using mobility aids shall be provided with back supports and armrests.

Grandstands and viewing areas.

32.—(1) Where exterior grandstands and viewing areas are provided, accessible seating spaces for persons using mobility aids shall be made available in all price ranges, as specified Figures 1.036,1.037 and 1.039 of the First Schedule to these Regulations.

(2) A grandstand shall have —

(a) a clear floor space of a minimum width of 900mm by depth of 1500mm, without reducing aisle space for side approach, and length of 1200mm for front or rear entry, as specified in Figure 1.036 of the First Schedule to these Regulations ; and

(b) accessible sitting areas for persons using mobility aids, with at least two spaces provided side by side, and a minimum of 3 *percent* of all spaces shall be reserved for persons using mobility aids.

(3) Seating areas shall be level, and of firm and of non-slip material.

(4) Where guardrails, handrails, or fences separate viewing areas from performance areas, care shall be taken to ensure that sightlines are appropriate.

(5) Fixed or portable seating in an amphitheatre for persons using mobility aids shall be provided with back supports and armrests.

(6) Seat heights shall be a maximum of 460mm and a minimum of 405mm, above floor level.

(7) An aisle leading to accessible seating area shall have a slope of a maximum of 1:20 at any point, and the walkway behind wheelchair positions shall be a minimum width of 1200mm.

(8) Viewing areas, including scenic lookouts, shall be accessible to persons using mobility aids.

(9) Where a pay-per-view viewing lense is available, at least one location shall be accessible to persons using mobility aids, and viewing lense and controls shall be mounted at a maximum height of 1200mm above grade.

Outdoor eating and entertainment spaces, balconies and terraces.

33.—(1) Exterior residential, and public balconies or terraces shall be accessible from interior spaces with thresholds not exceeding a height of 13mm.

(2) Where differences in elevation are unavoidable, short ramps with a maximum rise of 150mm, maximum pitch of 1 : 12, and a maximum length of 1200mm shall be utilized.

(3) Balcony or terrace surfaces shall —

(a) be of firm non-slip materials, and laid to slope gently at an angle of a minimum of 1 : 20 to ensure rapid removal of water ;

(b) have a depth of a minimum of 1830mm to allow free rotation of mobility aids, as specified in Figure 1.040 of the First Schedule to these Regulations ;

(c) be designed to allow for clear vision below the rails for persons in a sitting position ; and

(d) comply with Nigerian National Building Code requirements.

(4) Doors opening out onto balconies or terraces shall be located where they open against a sidewall or rail.

Boardwalks.

34.—(1) Where boardwalks are provided, including on a beach or waterfront locations, they shall be a minimum width of 1830mm to allow two wheelchairs pass with ease, as specified in Figure 1.041 of the First Schedule to these Regulations.

(2) Boardwalk surface shall be of firm and non-slip materials, and where wooden boardwalks are provided, planks shall be laid normal to the expected path of travel, having a maximum joint width of 6mm.

(3) Where the grade drop-off on a side exceeds 205mm, a contrasting and continuous stand-up edge of a minimum height of 1500mm shall be provided.

(4) A handrail or other suitable guard may be provided, where a grade drop-off exceeds 460mm.

(5) Roads, paths, sidewalks, or other pedestrian approaches to a boardwalk shall be accessible by a user of mobility aid through a level surface or ramped access point.

Campgrounds.

35.—(1) 5 *per cent* of boarding facilities on a campground shall be located close to essential amenities, such as toilets and bathrooms.

(2) A camp-ground shall be level with adjacent grades, be of a firm free draining surface, and have an obstruction free pathway.

(3) Picnic tables and barbecue pits shall be close to campground, and easily accessible by a mobility aid user, as specified in See Figure 1.043 of the First Schedule to these Regulations.

(4) A camp-ground shall be equipped with —

(a) accessible toilets and bathrooms or other campground amenities ;

(b) an accessible charging point ; and

(c) adjacent accessible parking, as specified in Figure 1.042 of the First Schedule to these Regulations.

Community mailboxes.

36.—(1) A community mailbox shall be located in conspicuous locations to a side of a pedestrian route or roadways.

(2) Parking spaces or lay-bys at community mailboxes shall include sufficient space for a wheelchair user's van.

(3) An accessible kerb ramp shall be provided to allow access from the road surface or parking locations by various mobility aids, as specified in See Figure 1.044 of the First Schedule to these Regulations.

(4) Community mailboxes shall be mounted on a level, firm, and free-draining surfaces, and have a minimum clear approach area of 1370mm by 1525mm.

(5) Numbers on mailboxes shall be at a minimum height of 19mm, and of a colour or tone that is distinguishable from the mailbox surface.

(6) Tactile markings and braille shall be provided at community mailboxes.

(7) Waste cans shall be located close to community mailboxes and placed to one side of the expected paths of travel.

Recreational Facilities.

37.—(1) Recreational facilities shall be accessible to persons with disabilities, as prescribed under these Regulations.

(2) In the case of a gymnasium, exercise machines and equipment shall have a clear floor space to allow for easy access and navigation.

Amusement rides.

38.—(1) Load or unload areas on an amusement rides shall have a ramp slope of a maximum of 1 : 8.

(2) Accessible routes connecting an amusement ride in the load and unload area shall have a vertical difference between the floors of 16mm, and the horizontal gap of a maximum of 75mm

(3) Wheelchair spaces shall be a minimum clear width of 760mm and a minimum clear length of 1220mm measured to a minimum height of 230mm above the floor surface.

(4) Where wheelchair spaces are entered into from the side, an amusement ride shall have a minimum maneuvering clearance of 950mm x 1220mm.

(5) Protrusion on an amusement ride shall be at a distance of —

(a) 150mm along the front of the wheelchair space, where wheelchair space is measured at a minimum width of 230mm and maximum height of 685mm from the floor surface ; or

(b) 635mm along the front of the wheelchair space, where wheelchair space is measured at a minimum of 685mm above the floor surface,

as specified in Figure 2.068 of the First Schedule to these Regulations.

(6) A seat on an amusement ride shall-

(a) be designed to allow for an independent transfer from a wheelchair ;

(b) be located at a maximum height of 430mm to 485mm above the load and unload surface ;

(c) be equipped with gripping surfaces and seat padding ; and

(d) be free of sharp objects or obstruction in the path of transfer.

(7) Where a series of transfer are required to reach a seat on an amusement ride the vertical transfer shall not exceed 205mm.

Recreational Boating Facilities.

39.—(1) An accessible route serving a boat slip such as a gangway or series of gangways shall comply with the provisions of regulation 8 of these Regulations.

(2) A boat slip may—

(a) have a clear pier space measuring a minimum width of 1525mm wide ; and

(b) for every maximum width of 3050mm linear pier edge serving the boat slip, contain a continuous clear opening of a minimum width of 1525mm wide.

(3) Notwithstanding the provisions of sub-regulation (2) of this regulation, clear pier space for a boat slip may be permitted at a minimum width of 915mm for a length of 610mm maximum, provided that multiple 915mm wide segments shall be separated by elements that are 1525mm wide minimum and 1525mm long minimum.

(4) Continuous clear openings on a boat slip shall have edge protection of a maximum height of 100mm and a maximum width of 51mm.

Docks.

40.—(1) Fishing, boating, or swimming docks shall be accessible to persons with disabilities, as specified in Figures 1.045 and 1.046 of the First Schedule to these Regulations.

(2) Paths, boardwalks and other routes to docks shall be made of level and firm material that provides direct access without elevation changes, and where sloppy road pavements are unavoidable, the gradient of the slope shall not be greater than 1 : 20, as specified in Figure 1.027 of the First Schedule to these Regulations.

(3) Grades steeper than 1 : 20 shall be designed as a ramp, with a slope gradient not greater than 1 : 12.

(4) Handrails shall be provided on both sides of a ramp from 1 :20 gradient, as specified in Figure 1.027 of the First Schedule to these Regulations.

(5) Sudden elevation changes of 205mm or less may be ramped at 1:8.

(6) A guardrail shall be provided, where dock surfaces, such as floating ducks, are located more than 460mm above the water surface.

(7) A contrasting stand-up edge of a minimum height of 150mm shall be provided on all exposed sides, where dock surfaces are 205mm or less above the water surface.

(8) Steps and ramps shall provide a safe entering position as specified in Figure 1.053 of the First Schedule to these Regulations.

Swimming pools and wading pools.

41.—(1) Outdoor swimming and wading pools shall be easily accessible.

(2) Swimming pools shall generally be of a "level-deck" designed to allow easy entry and exit from the pool.

(3) A stand-up edge provided around a pool’s perimeter shall be a minimum height of 205mm and maximum height of 405mm, and the top edge shall havea width of 305mm to allow for a seated person.

(4) Pool boundaries shall—

(a) be clearly defined by a textural change ;

(b) be of a bright colour or sharp contrast, to the water surface and the environment ; and

(c) have surrounding paving,

as specified in Figures 1.049 and 1.050 of the First Schedule to these Regulations.

(5) Materials and finishes used on the pool perimeter, deck, or on paved areas surrounding the pool shall be of firm and non-slip materials.

(6) Pool perimeter tiles or finishes shall be easy to clean and non-abrasive with chamfered edges at all pool boundary, to minimize the risk of injuries.

(7) The wall and floor of a swimming pool shall have a light-coloured finish for increased safety.

(8) Adequate floor drains that flush with the ground shall be provided on the pool deck to remove water quickly at all times.

(9) Drainage tile, scuppers, or trenches shall be designed to minimize accidental tripping, and have no openings greater than 13mm in diameter.

(10) Pool depth markings and signage shall be in highly contrasting colours and in large prints.

(11) Where diving boards or platforms are provided, they shall be distinctively marked and protected to ensure that persons with visual disabilities do not accidentally walk below them.

(12) Handrails shall be provided on both sides of access steps into the pool and extend a minimum length of 300mm onto the pool deck.

(13) Swimming pool's lanes or lane markers shall be in highly contrasting colours, and tie-off devices for lane markers shall be located where they do not constitute a potential tripping hazard.

(14) Starter blocks for competitive racing shall be securely fixed in place.

(15) Storage of safety gear or other equipment around the pool shall not be located where it constitutes a hazard.

(16) Lifeguard chairs or other pool-related furniture shall be painted in highly contrasting colours.

(17) Where there is no autonomous access into the pool, provision shall be made for transferring a person from a wheelchair into the pool, provided that where possible, permanent ramps shall be preferred to portable lifts.

(18) A built-in ramp into a pool shall be sloped at a maximum of 1:12, with handrails on both sides and be positioned, where it does not interfere with swimming lanes, as specified in Figures 1.047 and 1.053 of the First Schedule to these Regulations.

Sloped entries to a swimming or wading pool.

42.—(1) An alternative wheelchair made of corrosion resistant materials and specially designed for aquatic usage shall be provided to prevent pool contamination and prevent the damage to wheelchairs or other mobility aids.

(2) Where sloped entries are provided, the surfaces of a pool shall be slip resistant.

(3) A sloped entry of a swimming pool shall extend to a maximum depth of 760mm, below the stationary water level, and where landings are required, a minimum of one landing shall be located at the end of the slope, below the stationary water level.

(4) Sloped entry and landings in a wading pool shall extend to the deepest part of the pool.

(5) A slope entry into a pool shall —

(a) have two handrails of a width of 1050mm on both sides of a sloped entry ; and

(b) have on one side of the slope, a two-leveled handrail, with a clear width between handrails of 840mm minimum and 965mm maximum.

(6) A clear deck space of a minimum of 1525mm by 1525mm with a slope not steeper than 1 : 48 shall be provided at the base of the transfer wall, provided that the clear deck space shall be centered on the —

(a) grab bar, where one grab bar is provided ; or

(b) clearance between the grab bars, where two grab bars are provided.

(7) A transfer wall within the pool shall be—

(a) at a distance of a minimum of 405mm and maximum of 485mm, measured from the deck ;

(b) a minimum depth of 305mm and maximum of 405mm ;

(c) a minimum length of 1525mm ; and

(d) centered on the clear deck space.

(8) Surfaces of transfer walls shall not be sharp and have rounded edges.

(9) A minimum of one grab bar of 6.09mm width shall be provided on the transfer wall, and a grab bar shall be perpendicular to a pool wall and extends to full depth of the transfer wall.

(10) The top of the gripping surface shall be a minimum of 100mm and maximum of 150mm above transfer walls.

(11) Subject to sub-regulation (10) of this regulation, clearance space for a grab bar shall be a minimum of 610mm, as specified in Figure 1.052 and 1.053 to the First Schedule of these Regulations.

Transfer platform in a pool.

43.—(1) A transfer platform shall be provided at the head of each transfer system, and be of a minimum depth of 485mm and minimum width of 610mm.

(2) A transfer space of a minimum length and width of 1525mm with a slope not steeper than 1: 48 shall be provided at the base of a transfer platform surface, centered along a minimum of 610mm side of the transfer platform and the side of the transfer platform serving the transfer space shall be free from obstruction.

(3) Transfer step height shall be a maximum of 205mm, and the surface of the bottom tread shall extend to a water depth of a minimum of 455mm below the stationary water level.

(4) The surface of the transfer system shall not be sharp and shall have rounded edges.

(5) A transfer step shall have a —

(a) tread depth of a minimum of 355mm and a maximum of 430mm ; and

(b) a tread width of a minimum of 610mm.

(6) A minimum of one grab bar shall be provided on a transfer step or a continuous grab bar shall be provided on a flight of transfer steps.

(7) The top of the gripping surface of a single or continuous grab bar shall be a minimum of 100mm and a maximum of 150mm above a transfer step and transfer platform.

(8) The provisions of this regulation shall be as specified in Figures 1.055,1.056, 1.057, 1.058, 1.059 and 1.060 of the First Schedule to these Regulations.

Play grounds.

44.—(1) A playground shall have an accessible route from an accessible parking space with a clear width distance of a minimum of 1500mm, and a maximum slope of 1 :20.

(2) The clear width of accessible routes connecting elevated play components shall be a minimum of 915mm.

(3) Notwithstanding the provisions of sub-regulation (2) of this regulation, clear width of an accessible route connecting elevated play components may be reduced to a minimum of 815mm for a distance of a maximum of 610mm, provided the reduced width segment is separated by a segment that is of a minimum length of 1220mm and a minimum width of 915mm.

(4) The clear width of transfer platform connecting elevated play components shall be permitted to be a minimum of 610mm.

(5) A ramp shall be provided on a playground, —

(a) where slope exceeds 1:20,

(b) where the maximum slope for a ramp is 1:15, and

(c) with a minimum width of 1015mm, between handrails, for a maximum sloped distance of 9000mm.

(6) A landing shall —

(a) have a minimum of 2 *per cent* cross-slope to allow adequate drainage, and accommodate changes of direction or rest sites ; and

(b) comply with the provisions on ramps in these Regulations.

(7) The surface of a route on a playground shall be firm, slip-resistant, and capable of easy draining.

(8) For ease of supervision, play areas shall be separated according to age category by age-appropriate equipment, facilities, or other amenities.

(9) Play components shall be linked to an accessible route through the playground.

(10) A play component shall be situated in a designated location and free from obstruction.

(11) A play component which has a seat or entry point shall make provision for an unobstructed transfer from a mobility aid.

(12) A play table shall provide knee clearance with a minimum height of 610mm, minimum depth of 430mm, and minimum width of 760mm, and the tops of rims, curbs or other obstructions shall be of a maximum height of 785mm, as set out in Figures 1.063 and1.064 of the First Schedule to these Regulations.

(13) Amenities located on a playground such as public toilets and bathrooms, changing rooms, and telephones shall be accessible to persons with disabilities in accordance with the provisions of these Regulations.

(14) Resting furniture such as benches shall be located near paths and walkways.

(15) Grades in accessible picnic areas shall not be greater than 1 :30.

(16) Some accessible parking spaces shall be located within 30000mm to accessible picnic areas.

Terraces and patios of a public building.

45.—(1) Access from outdoor areas into interior areas shall be leveled, or have a sloped threshold not exceeding 13mm.

(2) Where there is grade difference of —

(a) 150mm or less, a short ramp of 1:20 shall be created ; or

(b) more than 150mm exists, a ramp of 1:15 shall be created.

(3) Terrace and patios shall be of firm and level materials laid to drain at slopes of not more than 1 : 50, and joints in patio or terrace materials shall be a maximum width of 6mm.

(4) A patio or terrace that is 600mm or more above grade shall have suitable guards, and the top rail of such guards or handrails shall allow a seated person to clearly see below the rail.

(5) Where a patio or terrace is 205mm to 460mm above grade, a cane detectable stand-up edge of a minimum height of 150mm, shall be provided.

(6) Where several patios or terraces are provided, wind and sun protection shall be required, for persons with disabilities who prefer to sit in a protected location.

Path and footbridges.

46.—(1) A path, and footbridge shall be as specified in Figure 1.066 of the First Schedule to these Regulations.

(2) Where a path or footbridge has a slope exceeding 1 : 20, an alternate route which consist of steps and ramps shall be provided nearby.

(3) Where steps, ramps, or footbridges are required, the -

(a) bridge surface shall be made of non-slip materials ; and

(b) bridge shall have handrails and guards,

as specified in Figure 1.068 of the First Schedule to these Regulations.

(4) A slope on a bridge shall not exceed 1 : 20.

Open Viewing location and instrument.

47.—(1) A viewing location, for viewing landmarks, special features, wildlife, entertainment and sports activities shall be accessible to a mobility aid user.

(2) A viewing instrument, such as telescope shall be lowered at a height of 1000mm for persons with disabilities.

Waterfront areas.

48.—(1) Waterfront areas in a park or other recreation facilities open to the public shall be designed to accommodate persons with disabilities.

(2) Provision for accessible parking area, entrance, path, and seating arrangement in a waterfront area shall conform with the provisions of these Regulations.

Wildlife reserves and conservation areas.

49.—(1) Wildlife reserves and conservation areas open to the public shall have accessible parking areas, entrances, paths, trails, and footbridges in line with the provisions of these Regulations.

(2) Rest areas shall be located near an accessible route and be equipped with the appropriate furniture, as specified in Figure 1.069 of the First Schedule to these Regulations.

(3) Clear sign post and other relevant indicators shall be provided to point out special lookout locations or wildlife viewing areas.

(4) A tactile map, including map with a raised outline, of paths and other features in a wildlife reserve or conservation area shall be provided at the start of the path and placed strategically along the path, as specified in Figure 1.070 of the First Schedule to these Regulations.

Market places.

50. Persons with disabilities shall have access to a market place.

Walkways and aisles.

51. A walkway or aisle between stalls or edges of vending tables shall be of a minimum width of 3000mm.

Vending tables.

52. A vending table or counter in a stall shall measure a maximum height of 1000mm and shall not protrude or obstruct the main pedestrian traffic flow.

Fire safety.

53.—(1) Provisions for fire prevention, protection and safety arrangements including means of escape shall be in accordance with fire safety standards issued by relevant authority.

(2) Access routes shall be created for fire tenders to access stalls and shall meet fire safety standards issued by relevant authority.

Access to seating area.

54.—(1) Access to seating in public waiting areas shall be direct and unobstructed and easily identifiable by persons with disabilities.

(2) Clear space for access to a seating area shall be of a minimum -

(a) width of 900mm in front of a row of seats or 1200mm where practicable, to allow access by persons with mobility aids along a cross-aisle as specified in Figure 1.071 of the First Schedule to these Regulations ; and

(b) width of 1050mm and minimum depth of 2300mm to allow for maneuvering a wheelchair into a designated space from a circulation route at right angles, as specified in Figure 1.072 of the First Schedule to these Regulations.

(3) A seating area shall be equipped with seats, and the seat height or the compressed cushion height for fixed seating, shall be between 450mm and 475mm.

PART IV—OUTDOOR AMENITIES

Access to outdoor amenities.

55. Outdoor amenities, facilities, or equipment shall be available to persons with disabilities.

Benches and seats.

56.—(1) Exterior benches or seats shall be located to a side of a public walkway or path, and be mounted on a leveled firm base, such as a concrete pad or brick pavers, as specified in Figure 1.083 of the First Schedule to these Regulations.

(2) A fixed bench shall measure at a height between 405mm and 460mm, as specified in Figure 1.083 of the First Schedule to these Regulations.

(3) A clearance area or space measuring 1015mm by 1220mm shall be available beside a bench.

(4) A bench shall have seats measuring a minimum length of 1065mm, minimum width of 510mm and a maximum depth of 610mm.

(5) Where practicable, a grab bar may be provided on a wall adjacent to a bench or seat to provide assisted transfer to bench, but not on the seat back, provided that the grab bar shall not obstruct transfer to a bench or seat.

(6) The surface of a bench or seat shall be slip-resistant and not accumulate water.

(7) The provision of this regulation shall be as specified in Figure 1.073 of the First Schedule to these Regulations.

Bicycle and motorcycle racks.

57. Bicycle and motorcycle racks shall be located to a side of a sidewalk, path, or entrance, and not constitute an obstruction.

Drinking fountains.

58.—(1) A public drinking fountain shall be securely mounted on a firm base, and have a clear knee space of a minimum width of 700mm, as specified in Figure 1.074 and 1.075 of the First Schedule to these Regulations.

(2) Where a drinking fountain is recessed or fitted, such as in an alcove, the—

(a) knee space below the fountain shall measure a minimum width of 760mm ;

(b) spout shall measure a maximum height of 915mm ; and

(c) controls shall be easily operable with one hand.

Accessible restrooms.

59.—(1) An accessible restroom shall be integrated within public toilet facilities, and separately accessible by men and women. .

(2) An accessible restroom shall be provided on each floor in a multi-storey building.

(3) An accessible restroom shall be—

(a) reached through an accessible circulation paths with clear directional signs ; and

(b) clearly labeled with the internationally recognised symbol of accessibility, together with written and tactile informative descriptions.

(4) An accessible restroom shall have a sliding door or a door that opens outwards to allow more space for a wheelchair to be maneuvered inside.

(5) The door referred to in sub-regulation (4) of this regulation shall have the capacity to be locked from the inside, and released on the outside in case of emergency.

(6) An accessible restroom shall —

(a) have a clear turning space measuring 1500mm by 1500mm to ensure easy navigation without obstruction ;

(b) be well-drained, and have waterproof, non-slippery and non-glare floor surface ;

(c) have sufficient natural and artificial light, good ventilation, and be free from loud background noise, strong smell, and flickering lights ; and

(d) have pull alarm system mounted on the ceiling near a toilet and suspended at a height of 1100mm from the floor.

(7) The colour of critical elements or facilities in an accessible restroom shall contrast with the background.

(8) A fire alarm shall be installed in the accessible toilet with visual and audible signals.

Toilet.

60.—(1) A toilet shall —

(a) be positioned in the corner of the room, and the centre line of the toilet shall be positioned at a maximum of 500mm from the sidewall ; and

(b) have a clear space measuring a minimum of 900mm on the open side of the toilet.

(2) A toilet seat shall measure at a maximum height of 480mm.

(3) The following equipment shall be easy to operate and shall be positioned near a toilet, at a maximum height of 1100mm above the floor—

(a) toilet paper dispenser ;

(b) flush control, where it is hand-operated ; and

(c) detachable bidet shower head.

(4) A sanitary bin shall be located near the toilet.

(5) A toilet shall have a —

(a) a moveable U-grab bar on the open side of the toilet ; and

(b) grab bar measuring a length of 600mm on the sidewall, located not more than 250mm from the rear wall and at a maximum height of 680mm.

(6) The provision of this regulation shall be as specified in Figure 1.077 and 1.078 of the First Schedule to these Regulations.

Washbasins.

61.—(1) A washbasin, soap, paper towel dispenser and hand sanitiser shall be provided near a toilet, at a maximum height of 1100mm from the floor.

(2) The rim of the washbasin shall measure a maximum of 740mm from the floor.

(3) A washbasin shall have a knee space underneath the washbasin.

(4) A tap shall be installed on a side of the washbasin and operable one-handed, with lever action and not twist action.

(5) A vertical grab bar shall be mounted around a washbasin.

(6) A mirror may be fitted above the washbasin, with the lower edge measuring a maximum height of 600mm from the floor.

Accessible washrooms.

62.—(1) In a public building, a minimum of one washroom equipped with accessibility features shall be reserved for persons with disabilities, as a stand-alone bathroom or incorporated within an accessible restroom.

(2) An accessible washroom shall be clearly labeled with the internationally recognised symbol of accessibility and relevant written informative description, and accessed through a clearly marked accessible path.

(3) An accessible washroom shall have a sliding door or a door that opens outwards to allow more space for a wheelchair to be maneuvered inside.

(4) The door referred to in sub-regulation (3) of this regulation shall have the capacity to be locked from the inside, and released on the outside in case of emergency.

(5) An accessible washroom shall —

(a) measure a minimum of 2000mm by 2200mm in size, with a clear turning space of 1500mm by 1500mm ;

(b) be well-drained, and have a waterproof, non-slippery and non-glare floor surface ;

(c) have natural and artificial light, good ventilation ; and

(d) be free from loud background noise, strong smells, and flickering lights.

(6) Lighting levels in a washroom shall be evenly distributed and no less than 100lux.

(7) A washroom and its compartments shall be as specified in and Figure 2.073 of the First Schedule to these Regulations.

Shower compartment.

63.—(1) A shower compartment shall —

(a) measure a minimum of 1200mm by 1200mm ;

(b) be fitted with a foldable seat measuring a maximum height of 480mm, with a backrest, and the centre line of the seat shall be positioned a maximum of 500mm from the sidewall ;

(c) be fitted with a curtain, which can be drawn while in a sitting position ; and

(d) be fitted with a pull alarm system mounted on the ceiling, and suspended at a height of 100mm from the floor.

(2) A folding grab bar shall be fixed —

(a) on the open side of a bath or shower seat, at a distance of 820mm from the sidewall, and at a maximum height of 680mm ;

(b) in front of a bath or shower seat at a distance of 900mm from the rear wall ; and

(c) on the wall on the side of a bath or shower seat.

(3) Where a washroom is fitted with a shower —

(a) a shower head shall be positioned at a —

(i) distance of 500mm from the rear wall, in the case of a fixed shower, or

(ii) maximum height of 1100mm and at a distance of 500mm from the rear wall, in the case of a detachable shower head ; and

(b) shower controls shall be located on the wall beside a shower seat, at a maximum height of 1000mm and distance of 500mm from the rear wall.

(4) Shower controls shall be easy to operate one-handed, with lever action and not twist action.

(5) The emergency alarm system shall be positioned inside the shower compartment, and be reachable and operable

(6) An easy to reach shelf and towel rail shall be positioned outside the shower compartment.

Bath compartment.

64.—(1) A bath compartment shall —

(a) measure a minimum length of 2440mm and minimum width of 1955mm ;

(b) be fitted with a bath tub, equipped with the following—

(i) a transfer seat measuring a minimum depth of 380mm, level with the bath rim and located at the end of a bath tub opposite the bath controls, and

(ii) a 915mm horizontal grab-rail, mounted at a height of 835mm on the long sidewall.

(2) The bath rim shall measure at a maximum height of 480mm from the floor level.

(3) Faucets and controls shall be of the "single-lever action" handle type.

Public telephones.

65.—(1) Where public telephones are provided in exterior settings, a minimum of one telephone shall be designed to be wheelchair accessible.

(2) A telephone shall be positioned on a side of a path of travel or walkway, clear of obstacles, and have clear space for access by persons using mobility aids.

(3) A telephone provided pursuant to these Regulations shall be —

(a) equipped to accommodate persons with disabilities, including persons with hearing disabilities ;

(b) equipped with teletypewriter telephone devices (TTY devices) ; and

(c) clearly marked with an internationally recognized symbol for persons with disabilities,

as specified in Figure 1.076 of the First Schedule to these Regulations.

(4) Where a telephone enclosure or recess is required the enclosure or recess shall measure a width of 760mm with knee space below the phone shelf or equipment measuring a minimum of 685mm clear.

(5) Telephone controls and slots shall be mounted at a maximum height of 1200mm, as specified in Figure 1.086 of the First Schedule to these Regulations.

PART V—OUTDOOR SUPPORT SYSTEMS

Zebra crossing and pedestrian signals.

66.—(1) Signals at pedestrian crosswalks shall —

(a) be designed in accordance with the requirements of the Nigeria Highway Code ;

(b) have a clearly marked pedestrian button to be mounted on a pole beside a curb cut, at a maximum height of 1065mm ; and

(c) be equipped with tactile features on pushbuttons, and audible and flashing crossing signals shall be provided, as an aid to persons who have hearing or visual disabilities.

(2) Visual display screen shall be visible enough to be seen, and audible pedestrian signals shall be loud and heard clearly above ambient noise at a minimum of 15 decibels louder than the ambient noise.

(3) The Commission, in collaboration with the appropriate authority, shall issue guidelines on the configuration of audible pedestrian signals, in line with international standards.

Lighting for exterior areas not including roads.

67.—(1) Exterior lighting on public thoroughfares and along pedestrian routes shall be designed in accordance with Nigerian Highway Code , as specified in Figures 1.080 and 1.081 of the First Schedule to these Regulations, and the lighting levels shall be a minimum of 30lux.

(2) Lighting sources shall be selected and located at, or beside steps and stairs to ensure clear definition of treads, risers, and nosing.

(3) Supplementary lighting shall be provided to highlight key way-finding signage.

(4) Lighting standard or post shall be mounted to a side of a path or walkway, and not constitute a hazard.

(5) An overhead light fixture shall be mounted on a standard with a clear headroom measuring height of 2030mm.

(6) Lighting of landscape on special site features shall be designed and installed to minimize direct glare, as specified in Figure 1.081 of the First Schedule of these Regulations.

(7) The Commission, in collaboration with the relevant authorities, may issue guidelines specifying lighting levels, colour spectrum, and other characteristics for light on public thoroughfares.

Public address systems.

68.—(1) Public address systems provided outdoors or at an exterior recreation or entertainment facilities shall be free from sound distortion, and provide a full spectrum of sound.

(2) Loudspeakers of an address system shall be located to cover the desired area adequately without feedback noise, and be mounted on posts to ensure that the output close to speakers is at acceptable acoustic levels for targeted audience.

(3) Where information is to be announced, a clear warning comprising both visual and audio signals shall be provided before the announcement.

(4) Where practicable, a Frequency Modulation (FM) loop or other suitable systems for persons with hearing disabilities may be provided where large outdoor concerts are regularly performed, as specified in Figure 1.082 of the First Schedule to these Regulations.

Way-finding.

69. Clear directional instructions that are easily perceived and understood with little or no assistance by persons with disabilities shall be provided.

Traffic signals.

70.—(1) Traffic light timing at specific sites shall be adjustable to —

(a) suit the volume of vehicular and pedestrian traffic ;

(b) suit walking speed of pedestrians, particularly of persons with disabilities ; and

(c) provide audible and visual cues,

as specified in Figure 1.079 and 1.083 of the First Schedule to these Regulations.

(2) A traffic signal shall -

(a) indicate when it is safe to walk or drive ;

(b) operate consistently with visible pedestrian signals ;

(c) in the case of an audible traffic signal, be capable of being heard above the ambient traffic noise levels ; and

(d) differentiate directional crossings.

(3) A pedestrian crossings signal shall be —

(a) capable of being activated by pedestrians waiting to cross ; and

(b) equipped with tactile features on a pushbutton , to aid persons who have both hearing and visual disabilities.

(4) A traffic light shall be mounted on a level surface that is identified with textured paving, and have buttons for pedestrian initiated calls.

(5) The button referred to in sub-regulation (4) of this regulations shall be—

(a) mounted at a height of 1065mm ;

(b) easily identifiable by colour and profile ; and

(c) equipped with a locator tone.

(6) Obstacles and free standing objects shall not be located on the level approach area or within 990mm of the normal pedestrian approach to the call button location, as specified in Figure 1.084 of the First Schedule to these Regulations.

PART VI—OTHER EXTERIOR FEATURES

Visual and tactile cues.

71. Visual and tactile cues shall be included in the design of the built environment for safe navigation.

Colour, pattern and texture.

72.—(1) Colour intensity and contrast with adjacent colours shall be utilized to —

(a) define boundaries of objects or to distinguish lettering from their background colour ; and

(b) provide information.

(2) Signage shall be designed using highly visible and contrasting colours, as specified in Figure 1.085 of the First Schedule to these Regulations.

(3) Colour or Tone contrast of approximately 70 *per cent* light reflectance shall be provided on signage, and finishes on signage shall be matte to minimize glare.

(4) Textured surfaces shall be used to indicate potential hazards, such as, level changes at ramps and stairs.

(5) For the purpose of a textured paving strip, a one pace depth of 915mm shall be provided at the head of stairs or ramps, or where a walking hazard may exist, as specified in Figure 1.086 of the First Schedule to these Regulations.

(6) Textured surfaces used as warning devices shall be cane-detectable, and clearly differentiated from surrounding paving surfaces, as specified in Figure 1.087 of the First Schedule to these Regulations.

(7) Textured surfaces such as saw-cut concrete, with regular grooves shall be positioned at a maximum distance of 50mm apart, with the grooves being perpendicular to the path of travel.

Construction site.

73.—(1) A construction site shall have a boundary protection to minimize hazard and provide easy access, as specified in Figure 1.086 of the First Schedule to these Regulations.

(2) A construction hoarding shall be firmly constructed with supports and bracing, which permits free movement by pedestrians, particularly persons using various mobility aids.

(3) Overhead framing or bracing shall ensure clear headroom of a minimum of 2030mm above the sidewalk.

(4) Cane detectable temporary barriers shall be provided around short-term repair sites, such as sidewalk repairs, manhole access cover, and etc., as an aid to

persons with visual disabilities, as specified in Figure 1.087 of the First Schedule to these Regulations.

(5) Where at a construction site or maintenance location, a clear pedestrian route of 1100mm is not achievable through the normal route, an alternative safe and level pedestrian routes shall be provided with suitable protection from vehicular traffic.

(6) Where hoardings with public viewing ports are provided, a minimum of one viewing port shall be mounted at a point not exceeding 1220mm on centre, for use by persons using mobility aids.

Freestanding objects.

74.—(1) Freestanding objects shall be located to a side of a pedestrian route, path, or walkway, designated amenity strips, or recesses without limiting the width of the route or constituting a hazard, as specified in Figures 1.088 and 1.089 of the First Schedule to these Regulations.

(2) Free standing objects include—

(a) permanent objects such as bollards, bicycle racks, benches, bus shelters, newspaper vending boxes, mailboxes, hydrants, light standards, trees, etc. ; and

(b) temporary objects such as queuing lines, sales booths, loose garbage receptacles, guy wires, etc.

(3) Objects with height between 685mm and 2030mm above the finished floor or ground shall not protrude beyond a length of 100mm into a circulation path, as specified in Figure 1.090 of the First Schedule to these Regulations.

Waste handling infrastructure.

75.—(1) A waste receptacle shall be —

(a) mounted in a designated location, and to a side of a pedestrian route, path, or walkway, so as not to constitute a hazard ; and

(b) accessible to persons using mobility aids, except for large industrial containers.

(2) A waste receptacle, container, or box, including recycling box, shallbe large enough to contain the anticipated quantity of waste in a location.

(3) A waste receptacle in a landscaped area, recreation, and picnic area shall be conspicuous and clearly identified by suitable colours or signage.

(4) The paving around waste receptacles shallbe level, firm, free draining. and easy to wash down.

(5) Where a covered waste receptacle is being used, the waste receptacle cover shall be easy to lift with one hand.

(6) Temporary construction scows or large mobile industrial containers shall be located away from normal pedestrian routes.

(7) Where a wall-mounted or recessed waste receptacle is being used, bin liners shall be easy to remove from the waste receptacle.

(8) Vehicular access routes to garbage containers for maintenance purposes shall not cross pedestrian routes.

Gates and openings.

76.—(1) Where a gate or opening is provided through a fence or screen to a public use area, such opening shall be accessible, and measure a minimum width of 915mm.

(2) Gate hardware shall be suitable for autonomous use, and closing devices shall not be spring-loaded.

(3) Where a turnstile or other ticketing device is not accessible, an accessible nearby gate or opening shall be provided.

(4) Gate openings shall be measured at minimum width of 815mm.

(5) Maneuvering clearances shall extend the entire width of a doorway and latch side or hinge side clearance, as specified in Tables 2.5 and 2.6. of the First Schedule to these Regulations.

Landscape materials and planting.

77.—(1) Plants with thorns and heavy berries shall not be located on or along the path of an active pedestrian route.

(2) Planter beds shall measure a maximum height of 460mm above grade, and planting bed edges adjacent to a busy pedestrian route shall measure a minimum height of 100mm.

(3) Overhanging branches of trees or shrubs, located over walkways or paths, shall be trimmed to ensure that the headroom over the walking space measures a minimum height of 2030mm, and pedestrian routes, paths, or walkways shall be clear of branches, thorns, and other obstructions at all times.

(4) An easement shall be provided at 20000mm from restricted areas.

Materials and finishes.

78.—(1) Paving surfaces for walkways and pedestrian routes shall be constructed using materials such as bitumen surface, concrete, interlocking bricks, or patio stones, provided that the joints connecting the paving surfaces do not exceed a width of 6mm, and the level variations do not exceed a height of 6mm in height.

(2) All paving shall be laid to drain easily.

(3) Gratings or grills shall be located on a side of a pedestrian route or walkway ; provided that, where it is impracticable to have gratings or grills on a side of the pedestrian walkway, gratings or grills shall be located at right angles to the normal path of travel, with openings measuring a maximum width of 13mm, as specified in Figures 1.095 and 1.096, of the First Schedule to these Regulations.

(4) Steps shall be of non-slip materials with highly contrasted nosings.

(5) Ramp surfaces shall be firm and of non-slip materials, and laid perpendicular to the path of travel.

(6) Handrails and guardrails shall be continuous, smooth and well maintained.

(7) Walls adjacent to ramps or stairs shall be in non-abrasive finishes.

Maintenance of outdoor features.

79.—(1) Pedestrian routes shall be well maintained to permit safe circulation of pedestrian movement.

(2) A pedestrian route or walkway leading to an accessible entrance and exit shall be kept free of obstacles.

(3) Garbage containers shall be emptied regularly to avoid the accumulation of extraneous materials around the containers.

(4) Light bulbs along pedestrian routes shall be replaced on a regular schedule, along with lamp having the same wattage.

(5) Gates, closers, automatic door operators, porch lifts, automatic ticket machines or other essential equipment shall be inspected and well maintained on a regular schedule.

Safety and security.

80.—(1) Lighting shall be provided over thoroughfares, steps and ramps, as specified in Figure 1.097 of the First Schedule to these Regulations.

(2) Pedestrian routes shall be designed to provide clear lines of sight to ensure personal safety wherever possible.

(3) The Commission shall, in collaboration with the relevant authorities, make guidelines for the provision of communication devices, alert systems, muster plan, and other emergency evacuation strategies.

CHAPTER THREE—REQUIREMENTS FOR INTERIOR OR INDOOR AREAS

PART I—ACCESS TO THE BUILDING

Pathway from a parking space to the building.

81.—(1) A pathway from a parking space to a building shall measure a minimum head height of 2100mm and a minimum width of 1200mm between a parking bay and a building

(2) Pathway surfaces shall be flat, firm, made of non-slippery materials, and kept clear of hazards and other obstacles at both ground level and higher level.

(3) An accessible ramp access point shall be provided, where there is a kerb along a pathway.

(4) Tactile paving strips shall be —

(a) used on public routes to assist persons with visual disabilities ; and

(b) of contrasting colours with the rest of the pavement.

Canopies and weather protection.

82.—(1) A main entrance and critical pathway connecting different parts of a facility shall be protected by a suitable canopy or overhang.

(2) A canopy projecting over a passenger boarding zone shall, provide a headroom clearance measuring a minimum of 3555mm to accommodate a special transit vehicle or other vehicle conveying persons with disabilities, as specified in Figure 1.098 of the First Schedule to these Regulations.

(3) Where a balcony is provided as part of a build environment, it shall be equipped to protect against wind, rain and sun.

Entrance.

83.—(1) Mobility aids shall be available on request at public buildings, and be positioned carefully so as not to constitute an obstruction.

(2) A tactile pictographic map of a building shall be installed near its entrance to provide a visual guide or information on the structure and parts of the building.

(3) Interior routes to accessible entrances and accessible exits shall be safe and easy to navigate by persons with disabilities.

(4) An entrance door shall —

(a) contrast visually with its immediate surroundings,

(b) be well lit and clearly signed ; and

(c) not have a mirrored finish.

(5) An accessible entrance shall —

(a) provide basic protection from the weather, and include doors and vestibules that are independently operated by persons with disabilities ;

(b) be fitted with security locks ; and

(c) be equipped with a communication device.

Reception area or information desk.

84.—(1) A reception area or information desk shall be located at a building entrance for easy identification, and access to the edge of a counter or reception desk shall be direct and unobstructed.

(2) Where a building provides a reception area or information desk, the area or desk shall be —

(a) clearly marked and identifiable from the entrance ;

(b) approached through an accessible path ; and

(c) designed to ensure the easy access of a wheelchair user and person with dwarfism.

(3) Where a reception area or information desk is fitted with a counter, a section of the counter shall—

(a) be lowered to a maximum height of 760mm and have a minimum width of 1500mm ;

(b) have a knee space measuring a height of 700mm from the floor and a depth of 500mm from the base of the counter ; and

(c) have a minimum work surface depth measuring 700mm.

(4) The front of the counter referred to in sub-regulation (3) of this regulation shall have a clear maneuvering space measuring a minimum depth of 1200mm and width of 1800mm, as specified in Figure 2.032 of the First Schedule to these Regulations.

(5) The accessible section of the counter shall be clearly marked with an internationally recognized symbol of accessibility.

(6) A reception area or information desk may, where practicable, provide—

(a) a hearing loop, and the hearing loop shall be clearly marked ;

(b) materials in accessible formats for persons with disabilities ; and

(c) sign language interpretation services.

(7) A knee recess to accommodate the feet of a wheelchair user and the footplate of a wheelchair shall be provided.

(8) Where queuing is the normal pattern of use, permanent or temporary control barriers shall be designed to allow for wheelchairs to—

(a) turn towards the counter or desk ;

(b) pass behind a person already in position at another window or desk ; or

(c) turn around and leave.

(9) Where the floor surface on the receptionist's side of a counter is on a higher level than on the visitor's side, a ramp with a gradient not greater than 1:20 or steeper, shall be provided to allow easy access.

Doors and doorways.

85.—(1) A main entrance door, and other accessible entrance and exit door shall measure a minimum width of 915mm to allow easy access of persons using mobility aids.

(2) Where an automatic door is in use, the door shall be defined by a highly contrasting colours and textured surface at grade.

(3) An entrance fitted with a door or any form of barricade shall be fitted with a guard measuring a minimum clearance of 305mm between the guard and the opened door or barricade, as specified in Figure 2.003 of the First Schedule to these Regulations.

(4) Where a building is finished with glazing materials, door frames shall be clearly colour-differentiated to aid in locating the entrance, as specified in Figure 2.004 of the First Schedule to these Regulations.

(5) The Commission, in collaboration with relevant agencies, may develop guidelines specifying the sizes and other specifications for doors and entrances.

Self-closing swing doors.

86.—(1) The minimum clear width of a single leafed door, or one leaf or the primary leaf of a double-leafed door, clear of any projections from the face of the door, shall be as shown in Table 2.4 of the First Schedule to these Regulations.

(2) Subject to sub-regulation (1) of this regulation, the method of measuring clear width shall be as specified in Figures 2.003 and 2.004 of the First Schedule to these Regulations.

Power-operated or automated doors.

87.—(1) A low energy power-operated or automated door shall be used as a swing door, and safety provisions for the low energy power-operated door shall conform to requirements of the relevant British Standard Code of Engineering.

(2) Where a building is fitted with revolving doors, a complementary accessible door, which is —

(a) low energy-operated or automated, or manual door ; and

(b) properly marked,

shall be provided immediately adjacent to the revolving door, and available for use at all times.

Double-leaf doors and gates.

88. Where a building is fitted with a double leafed door or gate, one of active leaves or primary leaf of the doors or gates shall comply with following—

(a) a door opening —

(i) shall measure a minimum clear width of 815mm,

(ii) in the case of swinging doors, shall be 90 degrees between the face of the door, when opened, and the stop, and

(iii) above a depth of 610mm shall have a minimum clear opening of 915mm ;

(b) no projection shall be permitted into a clear opening width lower than 865mm above the finish floor or ground, provided that where there is clear width of doors measured between 865mm and 2030mm, allowable projection shall not exceed 100mm above the finish floor or ground ;

(c) projection shall not exceed a maximum length of 16mm for the latch side stop ;

(d) a door closer and door stop shall measure at a minimum height of 1980mm above the finish floor or ground ;

(e) a minimum maneuvering clearance at a door or gate, which extends the full width of the doorway, and require latch side or hinge side clearance, shall comply with Table 2.1of the First Schedule of these Regulations ; and

(*f*) in the case of a hospital patient room, an entry door shall not be required to provide clearance beyond the latch side of the door.

Doorways without doors.

89. A doorway without a door or gate measuring less than 915mm shall have a manoeuvring clearance, and comply with Table 2.2. of the First Schedule of these Regulations.

Recessed doors or gates.

90. Maneuvering clearance for forwarding approach shall be—

(a) provided where an obstruction within 455mm of the latch side of a doorway projects more than 205mm beyond the face of the door ;

(b) measured perpendicular to the face of the door or gate ; and

(c) of equal floor level or ground surface, and changes in level shall not be permitted.

Door and gate hardware, locks and closers.

91.—(1) Where practicable, an automatic door opener may be provided.

(2) A pushbutton or card access control used to control a door or gate shall be—

(a) located away from the door swing ;

(b) mounted on a wall or post, at a height between 1000mm and 1100mm measured to the centre of the control from the ground level ;

(c) distinct in colour or texture on one side ; and

(d) brailed and have raised numbers or letters.

(3) A pushbutton shall measure 150mm in diameter.

(4) Doors in a series such as in a vestibule, shall measure a minimum of

2135mm apart, and the clear opening between door swings shall not be less than 1200mm.

(5) Door hardware, including pulls and push plates, shall be mounted between 915mm and 1065mm from grade.

(6) A door opening hardware in an entrance, vestibule, and room doors shall be easy to grasp and use, as specified in Figure 2.010 of the First Schedule to these Regulations.

(7) Hardware for closet doors, drawer pulls, and holders shall be of Simple 'D' type, with a range length of 75mm to 100mm, as specified in Figure 2.011 of the First Schedule to these Regulations.

(8) A door lock shall be mounted between the height of 760mm and 1065mm from ground level.

(9) A sliding door operating hardware shall —

(a) be exposed and usable from both sides ;

(b) be easy to grasp and use ; and

(c) not reduce the effective clear opening width below 810mm,

as specified in Figures, 2.009 and 1.071 of the First Schedule to these Regulations.

(10) Where out-swinging doors are being used, an additional pull handle shall be mounted horizontally, and close to the hinge side of the door.

Manual door opening and closing devices.

92.—(1) Door opening furniture shall be designed to be operated one-handed, with lever action and not twist action.

(2) Security and fire exit fittings, such as short lever turn buttons, bolts, latches or locks, shall be easy to handle or operate.

(3) Torque force required to operate a key and cylinder turn shall not exceed 0.5 Nm.

(4) For easy identification by persons with visual disabilities —

(a) a door hardware shall contrast visually with the surface of a door ; and

(b) a pull handle shall not be fitted on the push side of a door.

(5) The location and design of a lever and pull handles for both external and internal doors shall be as set out in Figures 2.011, 2.012, and 2.013 of the First Schedule to these Regulations, and be maintained consistently throughout a building.

(6) Where a lever intercepts a viewing panel, a projecting glazing bead shall not interfere with the operation of the lever or reduce the effective clearance behind it.

Controlled doors opening and closing devices.

93.—(1) For the purposes of access through a single or double swing door, the opening force of a door, when measured at the leading edge of the door, shall not exceed —

(a) 30 N from 0° of the door in the closed position to 30° open ; and

(b) 22.5 N from 30° to 60° of the opening cycle.

(2) A controlled door closing device, with or without a back check, shall allow the door to open sufficiently to provide the required effective clear width.

(3) The maximum closing force exerted by a controlled door closing device shall be within 0° and 15° of final closure.

Hinges.

94.—(1) A single-axis hinge and the fixing positions of a hinge shall conform to the requirements of the relevant British Standard Code of Engineering.

(2) Where it is necessary to minimize resistance to door opening and closing, hinges with low friction bearings shall be used to carry the appropriate mass of the door.

Locks and latches.

95.—(1) Locks, cylinders, and latches shall conform to the requirements of the relevant British Standard Code of Engineering.

(2) Where an upright mortise lock or latch is used, cylinder shall be placed above or below the lever handle, to ensure an unobstructed access to the keyway.

(3) Where, subject to sub regulation (2) of this regulation, a cylinder is placed below the handle, the minimum distance between the lever handle and the keyway of the locking mechanism shall be 72mm.

(4) The height of the lever handle shall be as specified in Figure 2.012 of the First Schedule to these Regulations.

(5) Where a multi-point locking system is used, it shall be capable of being locked and unlocked by a single turn of the key, and the operating height of a lever or pad handle shall be as specified in Figure 2.013 of the First Schedule to these Regulations.

(6) The Commission, in collaboration with the relevant authorities, may make guidelines specifying suitable locks cylinders and latches for use in buildings.

Door bolts

96.—(1) A door required to be bolted for security purposes shall have a at least one of the following bolts—

(a) knob slide flush bolts or surface bolts with a free moving slide action ;

(b) rack and pinion mortise bolts fitted with fixed knobs to enable the user to operate them easily without the need for inserting a loose key into a restricted hole ;

(c) surface-mounted or mortised espagnolette bolt with top and bottom shoots or side shoots, operated by a single handle positioned at a height between 900mm and 1050mm, from the finished floor level ; or

(d) lever-action flush bolts, provided that countersunk slide bolts, which are both flush and surface-mounted, shall not be used.

(2) A door bolt shall conform to the requirements of the relevant British Standard Code of Engineering.

(3) Release forces for panic exit devices operated by a horizontal bar for use on escape routes shall conform to the requirements of the relevant British Standard Code of Engineering.

(4) Release forces for emergency exit devices operated by a "Type A" lever handle and a "Type B" push pad shall conform to the requirements of the relevant British Standard Code of Engineering.

Glazed screens and sidelights.

97.—(1) Fully glazed sidelights at exterior entrances or in interior vestibules, and fully glazed screens used within a building, shall be clearly identifiable so as not to constitute a hazard for persons with visual disabilities.

(2) A row of bright decals or a continuous opaque stripe, measuring a minimum width of 50mm and of highly contrasting colour shall be mounted at eye level, between 1350mm and 1500mm from the finished floor.

(3) A decal shall—

(a) be located at a maximum of 150mm on centre ;

(b) be a minimum width of 50mm ; and

(c) with respect to the solid portion of the design or logo, be bold for easy identification by persons with visual disabilities.

(4) Where etched or patterned glass is being used, decals or stripes shall be of highly contrasting colours from the base.

(5) A partially glazed door shall have a glazed panel that extends low at a maximum height from grade 900mm to lower edge of glazing, in order to allow a person in a sitting position view the far side of the door, as specified Figure 2.014 of the First Schedule to these Regulations.

(6) Installation of a door at a doorway shall conform to the specifications in Table 2.2 of the First Schedule to these Regulations.

(7) A self-closing hinged or pivoted door across a passageway, which can be pushed to open in both directions, shall conform to the following --

(a) have controlled door closing devices, and allow for independent use ;

(b) a self-closing hinged or pivoted door, other than an entrance door across a passageway, shall have a viewing panel ; and

(c) a self-closing hinged or pivoted door on an escape route shall conform to the requirements of the relevant British Standard Code of Engineering.

(8) Glass doors may be used across passageways, provided that they shall conform to the following—

(a) a glass door or a fully glazed door with a narrow stile shall —

(i) be visible, with permanent manifestation within two zones measuring from 850mm to 1000mm from the floor and from 1400mm to 1600mm from the floor, and

(ii) contrast visually with the background seen through the glass in all light conditions ;

(b) the edges of a glass door shall be framed on both sides and the top, by an opaque high-contrast strip measuring a minimum width of 25mm to ensure that the door is visible ;

(c) where a glass door is adjacent to or is incorporated within a fully glazed wall, the door shall be prominent, and clearly differentiated from the wall ; and

(d) a glazed door should conform to the requirements of the relevant British Standard Code of Engineering.

(9) An architrave or frame lacking an architrave shall contrast visually with a wall surface surrounding the doorway.

(10) Where double doors of unequal width are used along the length of a passageway, the broader leaf shall be on the same side of the passageway throughout its length.

(11) A cross passageway fire-resisting door shall conform to the requirements set out in sub-regulations (9) and (10) of this regulation.

(12) A fire-resisting door shall be fitted with a controlled door closing device, irrespective of whether the door is latched or unlatched.

(13) For the purposes of this regulation —

(a) "self-closing hinged door" means a single swing door ; and

(b) "pivoted door" means a single or double swing door that is hinged from the bottom and top of a door.

Cupboard door hardware.

98.—(1) Door pulls or latches shall be of the lever handle or Simple 'D' type for easy use by persons with disabilities.

(2) Door hardware shall be mounted at a height not exceeding 1065mm.

(3) Where practicable, a handle shall be part of a lockset.

(4) Sliding cupboard or door hardware shall be mounted so that the remaining clear door opening is a minimum width of 860mm, as specified in Figure 2.016 of the First Schedule to these Regulations.

(5) Cupboard unit door and drawer handles shall be easy to grip.

(6) Cupboard unit doors shall swing open through 180° to allow for easy and unrestricted access.

(7) Where there is a shared kitchen facility, door pulls of high-level wall cupboards shall be positioned towards the bottom of the door.

(8) Sliding doors and drawers shall be capable of being operated with limited force when operated from the front or side.

Mats and mat sinkages.

99.—(1) Mats at entrances and in vestibules shall —

(a) be level with the floor surface ;

(b) be located in mat sinkages ; and

(c) have gently beveled edges,

so as not to constitute a tripping hazard, as specified in Figure 2.017 of the

First Schedule to these Regulations.

(2) Where a runner mat is used to define preferred walking routes or give directions, it shall lead directly to the target area, and the runner mat shall be clear of any obstacle intruding into the route.

(3) Runner mats shall be as continuous as possible, and in a contrasting colour or tone to the adjacent floor.

(4) A floor covering with large or repeating patterns that incorporate bold contrasting colours or simulate steps shall not be used on a floor surface.

Thresholds.

100.—(1) Thresholds shall be beveled, and not exceed a height of 13mm, where they are—

(a) located at interior doorways ; or

(b) required to accommodate floor level or finished changes to exterior areas.

(2) An existing or altered threshold with a maximum height of 19mm, which has a beveled edge on each side, shall have a slope not steeper than 1 : 2.

(3) An entrance threshold —

(a) may be level ; or

(b) where a raised threshold is unavoidable, such as to prevent water ingress, shall have one or more upstands and slopes, provided that the cumulative height of such upstands shall not exceed 15mm.

(4) An upstand that measures more than 5mm in height, shall have exposed edges, which may be chamfered or pencil rounded.

(5) Thresholds to internal doors shall be leveled at a junctions with different flooring materials.

(6) The provisions of sub-regulation (1) of this regulation shall be, as specified in Figure 2.020 of the First Schedule to these Regulations.

Vestibules.

101.—(1) An interior vestibule shall measure a minimum width of 1100mm to allow for easy navigation and turns at right angles through door openings.

(2) The depth of a vestibule shall be —

(a) a minimum width of 1200mm floor space to allow for the maneuvering of mobility aids ; and

(b) clear of door swings and other obstacles.

(3) Where a door swings towards a person using mobility aid, a minimum clear space of 600mm shall be available at the jamb, on the opening edge of the door, to ensure easy access to the door, as specified in Figure 2.018 of the First Schedule to these Regulations.

(4) Where a door swings away from a person using a mobility aid, a minimum clear space of 300mm shall be available adjacent to the jamb on the

opening edge of the door to ensure easy access, as specified in Figure 2.019 of the First Schedule to these Regulations.

Waiting areas.

102.—(1) A waiting area shall be leveled, and large enough to —

(a) accommodate a minimum of two wheelchairs users, furniture and other members of the public ; and

(b) allow persons using mobility aids to manoeuver.

(2) Seating furniture in a general waiting area in public and commercial buildings shall —

(a) measure between 450mm and 475mm in height ; and

(b) have arm rest or side supports.

(3) The provisions of subsection (2) of this regulation, shall not apply to seating furniture in closely seated public and commercial buildings such as auditorium, theatre, and cinema.

Seating layouts.

103.—(1) A seating layout shall be designed to —

(a) contain persons, including a minimum of two wheelchair users sitting next to each other ; and

(b) allow space, the size of a standard seat, within or at the end of a block of seating for an assistance dog.

(2) Where practicable, a mixture of fixed and removable seats may be provided to accommodate different seating layouts.

(3) In this regulation "assistance dog" include guide dogs and hearing dogs.

PART II—INTERIOR ROUTES

Interior circulation routes.

104. Interior circulation routes of a public building such as, passage ways shall —

(a) be wide enough to accommodate movement of persons, including persons using mobility aids ;

(b) except otherwise stated, have no unexpected level changes, and be free of obstruction ;

(c) have handrail support or resting place, where the internal circulation route is long ; and

(d) make provision for seats at intermediate points along the passageway, where the internal circulation route exceeds a length of 40,000mm.

Aisles and passageways.

105.—(1) In a low use public area such as a small office, a small hotel, and other buildings of like capacity, a clear aisle space or passageway between walls, glazed screen, furniture, or other fixed obstacle shall be a minimum width of 1200mm to accommodate the movement of a person, including a wheelchair user, as specified in Figures 2.020 and 2.021 of the First Schedule to these Regulations.

(2) In high use public area such as a mall, big hotel, hospital and other buildings of like capacity, a clear aisle, or passageway between walls shall be a minimum width of 1675mm to accommodate a minimum of two wheelchair users, as specified in Figure 2.021 of the First Schedule to these Regulations.

(3) Subject to sub regulation (1) of this regulation, where an aisle with a width of 1200mm is extensive in length or terminates in a dead-end, a turning space measuring a minimum length of 1600mm and minimum width of 1600mm shall be provided at 30000mm intervals and dead-end locations.

(4) In a high use public area, a passageway shall be a minimum width of 1675mm, and have a turning space of 1600mm in diameter, at every 20000mm interval, to permit the free movement, including a person using mobility aid as specified in Figure 2.022 of the First Schedule to these Regulations.

Projections into aisles and passageways.

106.—(1) A circulation route shall be free of obstruction, such as dust bin, radiator, fire extinguisher, or fire hose, provided that where an obstruction is fixed or required, the obstruction shall be guarded, as specified in Figure 2.023 and 2.024 of the First Schedule to these Regulations.

(2) Subject to sub regulation (1) of this regulation, an obstruction at the end of a circulation route shall be clearly marked with a warning sign, provided at the start of the route.

(3) Artificial lighting in a passageway shall be even, diffused and without glare, reflections or shadows, provided that artificial lighting for a passageway that receive no daylight shall be have illuminance at floor level of a minimum of 100lux.

Doors across passageways.

107. Doors across passageways shall comply with the provisions of regulation 85 of these Regulations.

Fire escape routes via horizontal circulation.

108.—(1) An unobstructed passageway leading to an escape route, shall be a minimum width of 1200mm.

(2) Escape routes shall conform to the requirements of the relevant British Standard Code of Engineering.

Lifts.

109.—(1) Lifts for use in a public building may be conventional passenger lifts, vertical lifting platforms, or stair-lifts.

(2) Where practicable, a public building with an existing stairway may be fitted with a non-enclosed lifting platforms to transfer a wheelchair user on a guarded platform vertically from one level to another.

(3) Lifts shall be designed to be accessible to persons using mobility aids.

(4) A lift shall —

(a) be equipped with an audio floor announcing feature ;

(b) have tactile controls or buttons, which are easy to reach and operate ;

(c) be fitted with a concave mirror installed at the back of the lift car ;

(d) be equipped with lighting, which illumination shall be a minimum of 100lux measured at the floor level ;

(e) be equipped with an emergency call system, with 2-way voice communication capability and an SMS facility, linked to a monitored location within the building ;

(*f*) have non-slip floor surface, and comply with the provisions of these Regulations relating to floor surfaces ; and

(*g*) comply with the relevant British Standard Code of Engineering.

(5) Adjacent lobby space at the lift entrance shall be equipped with lighting, which illumination shall be a minimum of 100lux measured at the floor level.

(6) A high-rise public residential building and public building shall be equipped with a lift of a minimum platform size measuring 1725mm by 2285mm, as specified in Figure 2.025 and 2.045 of the First Schedule to these Regulations.

Passenger lift.

110. A passenger lift shall comply with the following requirements—

(a) a lift keypad or information system call buttons, keypads, or SMS facilities shall be raised ;

(b) call buttons and keypads on a passenger lift shall be located as prescribed in Table 2.3 of the First Schedule of these Regulations ;

(c) call buttons, SMS facility, and keypads shall be located at a maximum height of 1370mm above the finished floor, measured to the centre line of the highest operable part ; and

(d) the size of a call button shall be a minimum width of 19mm in the smallest dimension.

Platform lifts.

111. —(1) A platform lift shall not be attendant-operated, and provide unassisted entry and exit from the lift.

(2) Entrance to a platform lift shall have a vertical clearance of 2030mm.

(3) The clearance between the platform sill and the edge of any runway landing shall measure a maximum width of 32mm.

(4) A platform lift shall have low-energy power-operated doors or gates.

(5) A platform lift serving a maximum of two landings and having doors or gates on opposite sides shall have self-closing manual doors or gates.

(6) A platform lift shall have a clear width of—

(a) 815mm, in the case of a lift with end doors and gates ; or

(b) 1065mm, in the case of a lift with a side door and gate,

as specified in Figures 2.026, 2.027 and 2.028 of the First Schedule to these Regulations.

Interior ramps.

112. —(1) Where there are minimal elevations within a building, an interior ramp shall be provided instead of a platform lift.

(2) An interior ramp shall have a maximum slope of 1 : 15, as specified in Figure 1.021, 1.022, 1.023 and 1,024 of the First Schedule to these Regulations.

Lighting platforms or daises.

113. Lighting platforms or daises provided for display or presentation purposes shall be accessible to and useable by persons with mobility aids.

Safe holding areas.

114. —(1) Where a safe holding area is included as part of the emergency plan for persons with disabilities, such holding area shall—

(a) be able to accommodate, among other persons, persons using mobility aids ;

(b) be located on each floor, above or below grade, which is easy to identify by persons with visual disabilities and be accessible to persons using mobility aids ;

(c) have separate emergency lighting and ventilation systems ; and

(d) have a two-way voice communication system linked to the fire control centre.

(2) Safe holding area within a stair lobby, passageway, or room adjacent to a stairway, shall be provided in accordance with the requirement relevant to the British Standard Code of Engineering.

Stairs and steps.

115. Stairs and steps within a building shall conform with the provisions of regulation 15 of these Regulations.

Turnstiles and control gates.

116. —(1) Where turnstiles or other crowd control gates are used to manage the movement of people, the turnstiles shall —

(a) be of a breakaway design to accommodate persons using wheelchairs or scooters ; or

(b) have an adjacent access gate that is wide enough to allow the passage of persons using mobility aids.

(2) Clearances at turnstiles or gates shall measure a minimum clear width of 860mm.

PART III—INTERIOR AMENITIES

Access to interior amenities.

117. Interior amenities shall be accessible by persons with disabilities.

Hanging racks.

118. —(1) Hanging racks shall be provided on every floor in a public building, and a 10 *per cent* of the hanging rack shall be reserved for and accessible to persons with disabilities

(2) A hanging rack shall have coat rods or coat hooks fixed securely and mounted at a height between 1200mm and 1370mm

(3) Clear door opening for closets fitted with a hanging rack shall measure a minimum width of 810mm to allow a frontal approach by persons using mobility aids.

(4) Where a public building or facility provides a public check-in counter for the storage of personal items, a section of the counter shall be lowered to comply with regulation 84 of these Regulations.

Drinking fountains.

119. —(1) Drinking fountains shall be accessible to persons with disabilities.

(2) Drinking fountains shall be set to one side of the path of travel with enough approach room for persons using mobility aids as specified in Figure 2.030 of the First Schedule to these Regulations.

(3) A wall-mounted or recessed drinking fountain shall have a clear knee space measuring a width of 765mm and a height of 735mm at the underside of the fountain.

(4) Controls for the drinking fountain shall be—

(a) mounted to one side of the bowl ;

(b) of a maximum height of 915mm ; and

(c) operable with one hand.

(5) The spout for water projection shall measure a maximum height of 915mm, with a trajectory across the bowl as specified in Figure 2.030 of the First Schedule to these Regulations.

Equipment and furniture.

120.—(1) The layout of furniture or equipment in the interior of a public building shall not constitute a hazard.

(2) Furniture, equipment, facilities, and planters, shall be positioned at the same side of the normal path of travel.

(3) Open seating such as a chair or bench shall measure between 405mm and 460mm in height.

(4) Seats with armrests and backrests shall be provided for persons with disabilities.

(5) Tables and desks shall be provided with a working surface measuring a maximum height of 785mm, minimum width of 760mm between supports, and a clear knee space height of 700mm, as specified in Figure 2.031 of the First Schedule to these Regulations.

(6) Planters with strong cane-detectable bases shall be used as specified in Figure 2.095 of the First Schedule to these Regulations.

Storage facilities.

121.—(1) Where in a public building storage compartments are being used, 10 *per cent* of the storage compartments shall be reserved for use by persons with disabilities.

(2) A storage compartment reserved for persons with disabilities shall —

(a) have the bottom shelf of the compartment measuring a maximum height of 1220mm and a minimum height of 460mm, from the floor ;

(b) measure a minimum width of 300mm and a maximum depth of 600mm ; and

(c) have a base set between 400mm and 800mm above floor level, as specified in Figures 2.035 and 2.036 of the First Schedule to these Regulations.

(3) subject to sub-regulation (2) of this regulation, a lock fitted for storage compartment shall be —

(a) mounted at height of 915mm from the ground, but not higher than 1065mm ; and

(b) easy to operate, one-handed, by persons with disabilities.

(4) Information inscribed on a storage compartment referred to in sub-regulation (2) of this regulation, such as name, number, or other information, shall be—

(a) mounted at a maximum height of 1525mm ;

(b) in distinct and legible lettering ; and

(c) on raised or recessed lettering format, and the colour of the lettering shall be highly contrasted from the background.

(5) Subject to sub-regulation (4) of this regulation, the size of the lettering or number shall be between 13mm and 19mm in height.

(6) A projecting door and drawer hardware of a storage facility shall contrast with the storage compartment and have no sharp edges.

(7) A storage compartment shall —

(a) contrast visually with its surroundings ;

(b) not have highly reflective surfaces ; and

(c) where practicable, be provided adequate lighting,

as specified in Figure 2.037 and 2.038 of the First Schedule to these Regulations.

(8) A compartment or carousel for luggage shall have a platform surface of a maximum height of 460mm from the floor.

Access to storage facilities.

122.—(1) Access to a storage facility shall be direct, free from obstruction, and where practicable, have sufficient space to allow free movement on the front and from the side, by person in a wheelchair.

(2) Where practicable, a storage facility shall be equipped with seats for persons with disabilities.

(3) The aisle clearance between opposing banks of storage compartments, such as a shelf storage units, filing cabinets or locker shall be a minimum width of —

(a) 1200mm, if knee space is provided ; or

(b) 1400mm, if no knee space is provided.

(4) Aisle space in front of a storage compartment or carousel shall measure a minimum depth of 1370mm to permit the forward or lateral approach by a person using mobility aid.

(5) Where practicable, a storage compartment shall be fitted with adjustable fixtures and fittings to ensure easy access by persons with disabilities.

Mailboxes.

123. The provisions of regulation 36 of these Regulations shall apply with regard to mailboxes located within public buildings..

Mirrors.

124.—(1) Mirrors located in public restrooms and bathrooms shall be available, and mounted at a height to enable for use by persons in wheelchairs.

(2) Subject to sub regulation (1) of this regulation, a mirror shall be mounted at a height such that the lower edge of the mirror over a washbasin measures a maximum height of 915mm from the floor, as specified in Figures 2.039 and 2.040 of the First Schedule to these Regulations.

(3) Notwithstanding the provisions of sub regulation (2) of this regulation, where it is not practicable to mount a mirror over a washbasin, a public restroom or bathroom shall be provided with a separate full-length mirror.

(4) Subject to sub regulation (3) of this regulation, a full-length mirror shall be mounted —

(a) at a height such that the lower edge of the mirror measure a height of 610mm from the floor and extend not less than 1830mm in height ; and

(b) where there is a clear floor area at a depth of 915mm by 1370mm in front of the mirror to ensure easy access by persons using mobility aids.

Restrooms and washrooms.

125. The provisions of regulations 59 to 62 of these Regulations shall apply with regard to restrooms and washrooms located indoors.

Work surface layout in a work station.

126.—(1) Except as expressly mentioned, a work surface shall be designed in an “L” or “U” shape, and where practicable, be continuous.

(2) There shall be a smooth transition between a work surface and other sections in a work station.

(3) Where in a self-catering kitchen or self-catering accommodation in a public residential building, occupied by persons using wheelchairs and other persons, the work surface of the kitchen shall be of two different maximum height levels of 760mm and 900mm, as specified in Figure 2.032 and 2.033 of the First Schedule to these Regulations.

(4) A work surface shall be of a maximum depth of 600mm and provide knee recesses with reduced work surface depth to allow wheelchair users reach over the work surface.

(5) Where practicable, work surfaces may be adjustable.

(6) The front edge of the work surface shall have a rounded profile.

Work surface accessories.

127.—(1) Where in a kitchen or workshop, circulation space is limited making it difficult to have an accessible work surface, pull-out boards shall be provided as a supplementary accessible work surface.

(2) A pull-out board shall —

(a) be fitted in a manner so as not to restrict the movement of users over a work surface ;

(b) be finished with rubber beading ; and

(c) contrast visually with the background when left in the "out" position.

Vending machines.

128. Where a vending machine is provided indoors —

(a) controls, dispensing areas, or other working parts shall be located at a

maximum height of 1200mm and at a minimum height of 465mm from the floor ;

(b) signage on a vending machine shall be in high contrast letters, and at a minimum height of 13mm ; and

(c) the floor space in front of vending machines shall be a minimum length of 1370mm by 1525mm,

as specified in Figures 2.042 and 2.043 of the First Schedule to these Regulations.

Windows and window hardware.

129.—(1) In a building designed with operable windows—

(a) the opening section of the windows shall be at a maximum sill height of 760mm from the floor ;

(b) windows with horizontal transoms shall be mounted at a height between 1070mm and 1200mm ; and

(c) window opening hardware shall be mounted at a maximum height of 1065mm,

as specified in Figure 2.044 of the First Schedule to these Regulations.

(2) Window hardware shall be designed to be operated one-handed, with lever action and not twist or rotary action.

(3) Windows in a public residential building shall be designed to deflect direct drafts away from an occupant when opened.

PART IV—INTERIOR SYSTEMS AND CONTROLS

Acoustic attenuating features.

130.—(1) Building materials that create echo sounds shall not be used in the construction of a public building.

(2) Where practicable, a public address or call system shall be located in critical areas of a building.

(3) Subject to sub regulation (1) of this regulation, building materials shall conform with the requirements of the relevant British Standard Code of Engineering.

Audible and visual information.

131.—(1) Essential audible signals, such as fire-alarm signals or elevator arrival call systems, shall be loud and distinct enough to be heard at a minimum of 15 decibels louder than the ambient sound as specified in Figure 2.046 and 2.047 of the First Schedule to these Regulations.

(2) Fire alarm signals in public buildings shall be designed with both visual and audio features.

Communication systems.

132.—(1) General, non-emergency, communication systems shall be accessible, useable and understood by persons with disabilities.

(2) A two-way communication system with voice input or output provided in a building shall include visual display.

(3) Communication systems, such as telephones, SMS facility relay and

intercoms, shall be equipped with volume enhancement, and where practicable, hearing loops for persons using hearing aids.

(4) Where practicable, information counters, enquiry and booking locations, may provide for the use of a TTY telephone, as specified in Figure 2.048 of the First Schedule to these Regulations.

(5) Signs that are designed to be read by touch shall not have sharp or abrasive edges.

(6) Characters contained in a communication system shall be—

(a) raised, and with a minimum height measuring 0.8mm above the background ; and

(b) bold and in uppercase font.

Braille.

133. Braille dots shall have a domed or rounded shape, and comply with Table 2.5, and Figures 2.049 and 2.050 of the First Schedule to these Regulations.

Symbols of accessibility.

134.—(1) Symbols of accessibility and their background shall have a non-glare finish.

(2) Symbols of accessibility shall contrast with their background as specified in Figure 1.033 of the First Schedule to these Regulations.

Controls and electrical installations.

135.—(1) Switches and controls within a building shall be easy to locate, operate and free from obstruction.

(2) Where applicable, a photo-luminescent pictogram sign shall be deployed to indicate or locate controls or operating mechanisms.

(3) Except as expressly mentioned, a control device shall be installed between 460mm and 1100mm above floor level, and be located at a minimum of 600mm away from the entrance or approach.

(4) A control device containing text or figures, or both shall be positioned at the angle of approximately 45° to the wall to ensure that the contents are easy to read and device easy to operate, such as, a panel in an elevator.

(5) A control device placed on a horizontal surface shall be placed at a height between 800mm and 900mm, and 300mm away from the edge of the surface.

(6) Subject to sub regulation (4) of this regulation, a control device shall be—

(a) located between a minimum height of 400mm and maximum height of 1000mm from the floor, in the case of socket outlets ; and

(b) mounted at a maximum height of 1200mm, in the case of light switches, thermostats and security controls.

(7) Controls and operating mechanisms shall be of a distinct colour or tone from the background.

(8) Information detailing the use or operation of controls or operating mechanisms shall be —

(a) in large print text on a highly contrasting background ; and

(b) mounted close to a control or operating mechanism.

(9) A raised pushbutton control shall be a minimum width of 13mm in diameter.

(10) The provisions of this regulation shall be, as specified in Figure 2.051 and 2.052 of the First Schedule to these Regulations.

Electrical power supply.

136.—(1) Electrical power design shall allow for supplementary lighting and communication devices to be added, where necessary.

(2) A public building shall provide emergency power to accommodate emergency and other vital operating components such as lighting levels, and lifts.

Fire emergency systems and signals.

137.—(1) Fire alarm systems shall be designed and installed in accordance with the relevant British Standard Code of Engineering.

(2) A fire alarm signal shall—

(a) be visible, as well as audible to users ;

(b) mounted high on the a wall ; and

(c) be easily visible against background colour and lighting.

(3) Fire alarm signal shall have —

(a) visible flashing signals ; and

(b) a distinctive sounds with two-stage evacuation distinguishable from each other in each stage as specified in Figure 2. 045 of the First Schedule to these Regulations.

(4) Fire-exiting announcement procedures shall be loud enough to be heard above ambient noise levels, and be preceded by a distinctive sound, in order to alert building occupants.

(5) The pulse of visible flashing signals shall be tested to ensure that it does not trigger epileptic seizures.

(6) A portable vibratory alarm shall be provided to supplement visual signals for persons, with disabilities.

HVAC and cooling systems.

138.—(1) Heating, cooling and ventilation systems shall be designed to accommodate persons whose respiratory systems are inadequate.

(2) Facilities serving persons with disabilities shall be designed to operate between—

(a) 21º C and 26º C temperature at all times of the year ; and

(b) 30 *per cent*—40 *per cent* humidity in the air.

(3) Mechanical ventilation and air-cooling systems shall not be mounted to allow the airflow from diffusers or grills to be directed towards a person lying in bed, seating, or working locations.

(4) Air handling system shall be mounted to be acoustically isolated to minimize noise.

Information systems and directories.

139.—(1) Information systems providing direct information to the public shall be comprehensible to persons with disabilities as specified in regulation 132 of these Regulations.

(2) Where auditory information is available, it shall be complemented by suitable printed material.

(3) Information on visual display screens shall be available in other formats, including audiotape or large print.

(4) Enlarged font shall be used on display monitors.

(5) Lighting levels at keyboards and other controls shall be evenly distributed at a minimum of 200lux intensity.

(6) Visual display screens in public information shall be mounted to ensure that there is no direct glare on the surface of the screen.

Artificial lighting.

140.—(1) Artificial lighting shall be installed—

(a) on the floors of all circulation routes ; and

(b) in all areas of potential hazard.

(2) Light sources and fixtures shall minimize direct and indirect glare from nearby reflective surfaces for users to navigate safely.

(3) Lighting shall be designed to ensure that the quality of light is close to a full spectrum.

(4) Light colour temperature between 27000K and 30000K shall be used to offset fluorescent or quartz light sources with a high blue content.

(5) Light fixtures with multiple points of high-intensity light shall not be used.

(6) The leading edges of stairs, steps, ramps, or escalators shall be evenly lit to minimize tripping hazards.

(7) Lighting levels in an lift or elevator lobby shall —

(a) be similar to the lighting levels in a lift or elevator cab in order to minimize tripping hazards ; and

(b) measure a minimum of 100lux intensity at the threshold of the elevator.

(8) Where practicable, emergency lighting over interior stairs and ramps, in exits or other paths of travel shall measure 100lux intensity at the walking surface and 50lux intensity at the exterior locations.

(9) Lighting over directional or informational signage such as at public telephones, informational or service counters, automated teller machines, or other keypad operations, shall measure a minimum of 200lux intensity at the working or information surface.

(10) Lighting over lecterns, podiums, platforms, or other speaker locations shall be capable of being enhanced, even when other lighting points are dimmed, to permit lip-reading and a view of any of the hand actions used to communicate.

(11) An artificial lighting system shall —

(a) be designed to be compatible with electronic and radio frequency installations ; and

(b) use high-frequency electronic ballasts to avoid any perception of flicker.

(12) Where practicable, uplighters with a light source at the floor or low level shall not be used as they cause glare and obscure vision.

Natural lighting.

141.—(1) Where practicable, natural light shall be utilized to assist in lighting entrances, passageway and major workspaces, and care shall be taken to minimize direct glare.

(2) Natural lighting shall be utilized in accordance with the relevant British Standard Code of Engineering.

Listening devices.

142.—(1) An FM loop or other assistive listening systems shall be —

(a) provided at meeting rooms, assembly and entertainment areas, serving more than 35 persons ; and

(b) provided with portable headsets compatible with personal hearing aids ;

as specified in Figure 2.055 of the First Schedule to these Regulations.

(2) Where infrared assistive listening devices are used, overhead lights shall not intercept infrared signal at the receiver.

(3) Dimmer switches and other transformer coils in meeting areas, shall be carefully located to prevent electromagnetic interference with any audio induction loop.

(4) Where an induction loop system is utilized, only half of the seating area shall be encompassed.

(5) A theatre or studio intended for viewing of motion pictures shall accommodate described video and the installation of rear-view captioning, in compliance with the Nigerian NBC.

(6) Larger meeting rooms shall be designed and furnished to allow a clear view of the speaker at all times.

Assistive listening systems.

143.—(1) In each assembly area where audible communication is integral to the use of the space, an assistive listening system shall be provided.

(2) Receivers shall be provided for assistive listening systems in each assembly area as specified in Table 2.6 of the First Schedule to these Regulations.

(3) Where all seats in an assembly area are served by an induction loop assistive listening system, the minimum number of receivers shall be as specified in Table 2.6 of the First Schedule to these Regulations.

Public address systems.

144.—(1) A public address system shall be —

(a) easy to hear above ambient background noise, without distortion or feedback ; and

(b) zoned to allow the direction of information to key locations only.

(2) A public address speaker shall —

(a) be mounted above head-level ; and

(b) provide adequate sound coverage in required areas.

(3) All-point call systems shall only be utilized for fire and emergency information.

(4) Personal alarm, and staff or other call systems shall be —

(a) selected with care and according to the requirements of the particular setting or user ; and

(b) used with discretion.

(5) Paging systems for use by staff or other key personnel shall be—

(a) be discreet and low in volume ; and

(b) only sound at locations, where such persons might reasonably be expected to be located.

Telephones.

145. The provisions of regulations 65 and 132 of these Regulations shall apply to this regulation and as specified in Figure 2.056 of First Schedule to these Regulations.

Signage and way-finding.

146. The provisions of regulation 69 of these Regulations shall apply to this regulation.

PART V—SPECIAL FACILITIES AND AREAS

Automated Teller Machines (ATMs).

147.—(1) ATMs shall be designed to be accessible for persons with disabilities.

(2) An ATM shall have a clear floor space in front and underneath it, measuring a minimum depth of 1220mm and minimum width of 915mm, and knee space height of 685mm, as specified in Figure 2.062 of the First Schedule to these Regulations.

(3) ATM controls, switches, panels, and card, coin, and cash location, shall be mounted at a maximum height of 1000mm from the floor level.

(4) Control buttons, and coin or card access locations on an ATM shall—

(a) be easily identifiable ;
(b) have tactile features, and raised numbers or letters ; and
(c) be distinctively coloured.

(5) An ATM shall be equipped with —

(a) audio accessibility devices to provide voice or sound cues or instructions; and

(b) volume controls for persons with hearing disabilities.

Ticketing machines.

148.—(1) Ticketing machines for parking, fares, admission, and general services shall be accessible to persons with disabilities.

(2) Operable or dispensing parts of a ticketing machine shall measure a maximum height of 1200mm and minimum height of 915mm, from floor level.

(3) Control buttons, and coin or card access locations shall —

(a) be easily identifiable ;

(b) have tactile features, and raised numbers or letters ; and

(c) be distinctively coloured.

Video and image display terminals.

149. The provisions of regulation 139, 142, and 143 of these Regulations shall apply with regard to video and image display terminals.

Restaurants and other eateries.

150.—(1) A restaurant or other eating area offering food services to the public shall be accessible to persons with disabilities.

(2) Aisle spaces between furniture, equipment, or other fixed objects shall measure a minimum width of 900mm, as specified in Figure 2.066 of the First Schedule to these Regulations.

(3) A reception area or information desk, and cashier point of a restaurant or other eating area shall comply with the provisions of regulation 84 of these Regulations.

(4) A restaurant or other eating area, where food services are provided shall conform to the following —

(a) food displays shall be mounted on a surface with a minimum height of 915mm from the floor ; and

(b) overhead display shelves shall measure a maximum height of 1220mm from floor level, as specified in Figure 2.035 of the First Schedule to these Regulations.

(5) Drink dispensing areas shall comply with the provisions of regulation 119 of these Regulations.

Place of Worship.

151.—(1) Places of worship including main areas of worship, meeting rooms, restrooms and bathrooms, and offices shall be accessible to persons with disabilities.

(2) Seating areas or praying spaces within a place of worship shall comply with regulation 54 of these Regulations.

(3) Notwithstanding the provisions of sub-regulation (2) of this regulation, a minimum of 8 *per cent* of seats or praying spaces in a place of worship shall be reserved for persons with disabilities.

(4) Ablution area or spaces shall be accessible to persons with disabilities, and conform to bathroom specification prescribed in regulation 59 to 64 of these Regulations.

Public institutions in the criminal justice system.

152. Public institutions such as a court, police station, or correctional center shall ensure that information is provided in accessible format as set out in these Regulations.

Health Care and social welfare facilities.

153. A facility that provides healthcare or social welfare services to the public shall be accessible to persons with disabilities, as prescribed under these Regulations.

Libraries.

154.—(1) A facility that provides library services to the public shall be accessible to persons with disabilities, as prescribed under these Regulations.

(2) Book return and checking area counters shall conform to the provisions of regulation 84(3)(4), (7)-(9) of these Regulations.

(3) Book shelves shall have an aisle space measuring a minimum width of 1065mm, as specified in Figure 2.063 of the First Schedule to these Regulations.

(4) Lighting at book shelves shall be mounted directly over the aisle space and provide a minimum of 200lux at normal working height of 915mm.

(5) Study tables shall measure a maximum depth of 600mm, and provide knee space with a minimum height of 700mm.

(6) Shelves constructed over study tables shall be of a maximum height of 1000mm from the table.

Schools and Education Centres.

155. Schools and other education centres shall comply with the provisions of these Regulations.

Public residence.

156.—(1) A public residence shall comply with the provisions of these Regulations.

(2) A public residence shall be equipped with a fire alarm system, which wiring system shall be connected to a smoke detection system.

(3) Fire alarm system in a public residence shall comply with the provisions of regulation 137 of these Regulations.

(4) The main entrance of a public residence shall be equipped with —

(a) communication features, which shall include a two-way communication system, and where practicable, a visual display screen ;

(b) a hard-wired electric doorbell, which shall—

(i) initiate an audible tone and visible signal, and

(ii) have controls to deactivate the signal, where the bell is located in sleeping areas.

(5) An entrance door to a residential unit of a public residence shall be fitted with a peep hole that allows for a minimum of 180-degree range of view and clarifies the image in view.

(6) Where a residential unit of a public residence that is designed to be accessible is located on—

(a) an upper floor, it shall be located close to a lift ; or

(b) the ground floor, it shall be located close to the reception area or main entrance.

Kitchen in a public residence.

157.—(1) A kitchen in a public residence shall comply with the provisions of these Regulation, and in particular—

(a) have an aisle between counters with a minimum width of 1065mm ;

(b) where practicable, have a turning space in dead-end areas, with a minimum width of 1500mm ; and

(c) have clear knee space below counters,

as specified in Figures 2.069, 2.070, 2.071, and 2.072 of the First Schedule to these Regulations.

(2) A kitchen stove may be fitted with front or side regulator control, or where practicable, an automatic switch control.

(3) A clear counter space with a minimum width of 300mm shall be provided on both sides of a stove to ensure safe operation.

(4) Where a cabinet is located under a work surface—

(a) the cabinet shall be capable of being removed without tampering with, removing, or replacing the kitchen work surface ;

(b) the finished floor shall extend under the cabinet ; and

(c) the wall behind and surrounding the cabin shall be finished.

Special washroom in a public residence.

158.—(1) A residential unit of a public residence that is designed to be accessible may comply with the provisions of this regulation.

(2) A washroom that incorporates a corner water closet layout for independent use shall be as specified in Figures 2.077 and 2.078 of the First Schedule to these Regulations.

(3) A washroom equipped with a ceiling-mounted full room cover, tracked hoist system for assisted service shall be as specified in Figure 2.075 of the First Schedule to these Regulations.

(4) A washroom allowing for —

(a) assisted use of a bath, without hoist, and a peninsular water closet shall be as specified in Figure 2.073 and Figure 2.078 of the First Schedule to these Regulations ; or

(b) assisted use of the bath and WC, with space for a mobile hoist operated by an assistant, shall be as specified in Figures 2.078 and 2.079 of the First Schedule to these Regulations.

Bedroom in a public residence.

159.—(1) A bedroom in a public residence shall comply with the provisions of these Regulations.

(2) Where a public residence has provision for an accessible bedroom, the bedroom—

(a) may be furnished with en-suite toilet and bathroom facility ;

(b) shall be capable of being adapted to suit accessibility needs ;

(c) shall be free from obstruction ;

(d) shall be located close to the entrance door ;

(e) have a clearance space measuring a minimum length of 1500mm and minimum width of 1500mm on one side of a bed ;

(*f*) shall be furnished with a bed—

(i) which frame shall measure a maximum height of 480mm from floor level, an a minimum clearance under the bed of 150mm, and

(ii) which shall not have extra legs midway between the corner legs ;

(h) shall be furnished with a firm mattress ; and

(i) may be equipped with under-pillow vibrating units or vibrating under-mattress pads that plug into the fire alarm system.

(3) Furniture and fittings in a bedroom shall contrast with their surroundings.

(4) Notwithstanding the provisions of sub-regulation (2)(*a*) of this regulation to furnish an accessible room with an en-suite toilet and bathroom provided shall comply with the provisions of these Regulations.

Shops and shopping malls.

160.—(1) Shop, shopping malls, and other building where goods and services are provided shall comply with the provisions of these Regulations.

(2) A shopping mall shall provide close to its entrance, a drop off or setting-down point.

(3) The drop off or setting-down point referred to in sub-regulation (2) of this regulation shall have a raised kerb, which runs along the length of the drop off or setting-down point bay width.

Accessible cabin coach.

161.—(1) A train shall have a minimum of one accessible cabin coach.

(2) An accessible cabin shall —

(a) have an accessible restroom,

(b) be equipped with an on-board wheelchair ; and

(c) have an aisle measuring a width of 900mm.

Part VI—Other Interior Features

Life safety plan.

162. A building shall, at its entrance, provide an evacuation plan and mustering strategies.

Maintenance.

163. A person to whom these Regulations apply under regulation 2 of these Regulations shall develop a maintenance manual for use.

Chapter Four—Enforcement and Compliance

Inter-agency collaboration.

164. The Commission shall collaborate with relevant MDAs and professional bodies to ensure compliance with the provisions of these Regulations.

Compliance procedures.

165.—(1) A person to whom these Regulations apply under regulation 2 of these Regulations shall, prior to a new construction, present a construction plan to the relevant authority to ensure that the plan conforms with the standards and code for an accessible built environment, as set out in these Regulations.

(2) The Commission may issue a provisional accessibility compliance certificate, where satisfied that the relevant authority approved the construction plan submitted under sub-regulation (1) of this regulation.

(3) The Commission shall conduct an accessibility audit on a built environment existing prior to the commencement of these Regulations upon the

expiration of 21 days accessibility audit notice issued by the Commission to an owner or occupier of the built environment.

(4) The Commission may issue a National Accessibility Compliance Certificate—

(a) where satisfied that a built environment referred to in sub-regulation (3) of this regulation complies with the provisions of these Regulations ; and

(b) on the payment of prescribed assessment fees, as may be determined by the Commission.

(5) A National Accessibility Compliance Certificate issued by the Commission shall be valid for a period of five years.

(6) The Commission shall monitor compliance of these Regulations, and report any non-compliance to —

(a) the Secretary to the Government of the Federation, in the case of an MDA ; and

(b) a relevant authority, in the case of a person under regulation 2 of these Regulations, other than an MDA.

National Disability Compliance Certificate.

166.—(1) A person to whom these Regulations apply under regulation 2 of these Regulations shall, from the commencement of these Regulations, apply to the Commission for the National Disability Compliance Certificate.

(2) The Commission shall issue a National Disability Compliance Certificate where it is satisfied—

(a) that an applicant has completed the certification course referred to in regulation 167 of these Regulations ;

(b) with an applicant's compliance with the provisions of the Act and these Regulations ; and

(c) that an applicant has paid the prescribed fees.

(3) A National Disability Compliance Certificate shall be valid for a period of one year.

(4) The Commission shall issue a penalty on the renewal of a National Disability Compliance Certificate where a person fails to renew the certificate within 90 days of its expiration.

(5) The Commission may withdraw a Certificate issued under this regulation, where it was obtained contrary to regulation 167(2) of these Regulations.

(6) The National Disability Compliance Certificate is a mandatory pre-qualification document for bidding on procurement of public works, goods, and services.

Capacity building on accessibility and compliance.

167.—(1) The Commission may, by itself, conduct or approve the conduct of a certification course on accessibility and inclusive development.

(2) The attendance and completion of the certification course referred to in sub-regulation (1) of this regulation is mandatory and a condition for the issuance of a National Disability Compliance Certificate.

(3) The certification course referred to in sub-regulation (1) of this regulation and the National Disability Compliance Certificate issued by the Commission shall be mandatory requirement for the registration of any person with relevant expertise by the Corporate Affairs Commission and other relevant Regulatory Institutions.

Administrative penalty.

168.—(1) Notwithstanding the penalties provided under the Act or any other law, any person who contravenes the provisions of these Regulations is liable to an administrative penalty of not less than ₦500,000.

(2) Any company, government institution or body corporate that contravenes the provisions of these Regulations is liable to an administrative penalty of not less than ₦2,000,000.

(3) The Commission may by guidelines prescribe a scale of fees for services rendered under these Regulations.

(4) Fees chargeable and administrative penalties payable under these Regulations shall be paid into the Fund established under the Act.

Powers to seal off building.

169.—(1) Notwithstanding the provisions of regulation 168 of these Regulations, the Commission, in collaboration with a relevant authority, may seal off a built environment found to be in default of the provisions of these Regulations or the Act.

(2) Prior to the exercise of its powers under sub-regulation (1) of this regulation, the Commission shall issue an owner, manager, occupier, or developer of the built environment in default a 90 day notice to regularize the default.

Chapter Five—Miscellaneous Provisions

Issuance of guidelines.

170. The Commission may, from time to time, issue guidelines or circulars for the implementation of the provisions of these Regulations.

Interpretation.

171. In these Regulations—

"*Act*" means Discrimination Against Persons with Disability (Prohibition) Act 2018 ;

"*Call system*" means communication technology that allows persons to send signal or information ;

"*Commission*" means the National Commission for Persons with Disabilities ;

"*Drinking fountain*" means a device or receptacle that produces a stream of water or other liquid drink for people to drink from ;

"*Mobility Aid*" means a device designed to assist walking, including, wheel chair, scooter, guide cane, crutches and any other device used to improve the mobility of people with a mobility disability ;

"*National Accessibility Compliance Certificate*" means the certificate issued by the Commission to a person referred to under regulation 2 of these Regulations upon satisfactory compliance with the provisions of the Act and regulation 165 (4) of these Regulations ;

"*National Disability Compliance Certificate*" means the certificate issued by the Commission to a person referred to under regulation 2 of these Regulations upon satisfactory compliance with the provisions of the Act and regulation 165(4) of these Regulations ;

"*Passageway*" means a long, narrow way, typically having walls either side, that allows access between buildings or to different rooms within a building, and includes a corridor and hallway ;

"*Pedestrian route*" includes walkway, pathway ;

"*Playground*" includes picnic area, park ;

"*Public Building*" means buildings used by the public such as hospitals, schools, malls, shops, stores, estates, worship places, fuel stations, hotels & restaurants, offices, recreation and sports centers ;

"*Two-way communication*" means the process of sharing information back and forth between two parties ; and

"*Wheel chair*" includes a motorized wheelchair, scooter, handcycle, etc.

Citation.

172. These Regulations may be cited as the Persons with Disabilities (Accessibility) Regulations, 2023.

FIRST SCHEDULE

FIGURES, SYMBOLS AND TABLES

PART 1 : EXTERIOR OR OUTDOOR AREAS




Figure 1.001: Kerb ramps at walkways




Figure 1.002: Pedestrian Pushbuttons

Figure 1.003: Kerb ramps




Figure 1.004: Kerb ramp on a public thoroughfare

Figure 1.005 Kerb Ramps - CURB DEPRESSION

Figure 1.006: Cane detectable kerb ramps for persons with visual disabilities

Figure 1.007: Locational aid for persons with disabilities



Figure 1.008: Handrail or guard for persons with disabilities



Figure 1.009: Mounting of Handrails (a)

Figure 1.009: Mounting of Handrails (b)




Figure 1.010 Stairs supplemented with ramps





Figure 1.011 Double handrails at different heights

Figure 1.012: Vertical clearance

Figure 1.013: Special lay-by area






Figure 1.014 Bus boarding and alighting areas




Figure 1.015 Bus shelters




Figure 1.016: Mounting of unit paving materials




Figure 1.017: Gratings located in sidewalks

Figure 1.018: Obstacle-free routes




Figure 1.019: Projections into an access route that does not need hazard protection




Figure 1.020: Projections into an access route that need hazard protection




Figure 1.021: Intermediate Level Landings




Figure 1.022: Doors opening onto Ramps returning upon themselves

Figure 1.023:Ramps

Figure 1.024: Handrails on Ramps





Figure 1.025: Paving surfaces at the flight of stairs or steps

Figure 1.026: Traffic islands

Figure 1.027: When slopes shall be treated as ramps

Figure 1.028: Bus/public transit shelters







Figure 1.029: Accessible parking spaces

Figure 1.030: Two accessible parking spaces adjacent to each other



Key
1 Preferred access route avoiding travel behind parked cars
2 Dropped kerb or level access
3 Standard 2 400 mm × 4 800 mm designated parking space
4 1 200 mm wide safety zone for boot access and cars with rear hoists, outside the traffic zone
5 1 200 mm wide marked access zone between designated parking spaces

Figure 1.031: Access around designated off-street parking spaces




Figure 1.032: Markings for multiple designed off-street parking spaces (Dimensions in millimeters)




Figure 1.033: Symbols of accessibility




Figure 1.034: Position of Clear Floor or Ground Space




Figure 1.035: Maneuvering Clearance in an Alcove,





Figure 1.036: Location of wheelchair spaces in front of a rear aisle (Dimensions in millimetres)



Key
1 Rostrum
2 The rostrum as well as seats on the rostrum and seats in the next row can be removed to create more wheelchair spaces
3 (1 400 × 900) mm nominal wheelchair spaces
4 Rear wall
5 Aisle
6 Steps

Figure 1.037: Location of wheelchair spaces at a seat way (Dimensions in millimetres)

Figure 1.038: Accessible seating spaces

Figure 1.039: Provision of two wheelchair positions in grandstands and viewing areas

Figure 1.040: Balcony depths that allow free rotation of mobility aids



Figure 1.041: Boardwalks for the use of two persons in wheelchairs

Figure 1.042 Accessible campsites

Figure 1.043: Wheelchairs accessible to picnic tables and barbecue pits

Figure 1.044: Kerb ramps accessible to mailbox

B 1430

Figure 1.045: Accessible fishing dock

Figure 1.046: Accessible entry to dock

Figure 1.047: Handrails on both sides of access steps into the swimming pool and steps/ ramp

---

Figure 1.048: Handrails extension onto the pool deck

Figure 1.049: Pool boundaries defined by textural change




Figure 1.050: Pool boundaries clearly defined by bright colour to the water surface/ surrounding paving

Figure 1.051: Guardrails and recessed steps into swimming pools




Figure 1.052: Sloped entry submerged depth




Figure 1.053: Handrails for sloped entry




Figure 1.054: Clear deck space at transfer walls




Figure 1.055: Transfer wall height




Figure 1.056: Depth and length of transfer walls




Figure 1.057: Grab bars for transfer walls




Figure 1.058: Size / Clear deck space of the transfer platform




Figure 1.059: Transfer steps / Size




Figure 1.060: Grab bars

Figure 1.061: Accessible Play areas and recreational equipment for children

Figure 1.062: Low platforms for transfer onto the play equipment

Figure 1.063: Approach access to picnic tables from both ends



Figure 1.064: Plan view/ Knee and armrest of picnic table



Figure 1.065: Controlled access point

Figure 1.066: Accessible pedestrian paths and footbridges with trail

Figure 1.067: Accessible viewing area

Figure 1.068: Non-slip materials for bridge's surface

Figure 1.069: Rest areas /lay-bys with seating




Figure 1.070: Tactile map of path and features




Figure 1.071: Space needed to allow access by people using crutches (Dimensions in millimetres)




Figure 1.072: Spaces for wheelchair users in a general seating layout (Dimensions in millimetres)




Figure 1.073: Exterior benches or seats mounted on a firm and level base

Figure 1.074: Exterior public drinking fountains with clear knee space




Figure 1.075: Drinking fountains and water coolers

Figure 1.076: Telephones with International Symbol

Figure 1.077: A door to a toilet with clear width




Figure 1.078: Plan view of accessible toilet

Figure 1.079: Pedestrian Traffic Signals

Figure 1.080: Exterior lighting illuminance

Figure 1.081: Non glare light

Figure 1.082: Public address systems with FM Loop




Figure 1.083: Traffic lights and signals




Figure 1.084: Obstructions free to call button locations

Figure 1.085: Textured paving strips

Figure 1.086: Boundary protection to minimize hazards

Figure 1.087: Cane detectable temporary barriers

Figure 1.088: Designated pedestrian route

Figure 1.089: Temporary objects being located to one side of normal pedestrian route




Figure 1.090: Limits of protruding objects




Figure 1.091: Clear width of doorways




Figure 1.092: Maneuvering clearances at manual swinging doors and gates




Figure 1.093: Manoeuvring clearances at doorways without doors, sliding doors, gates and folding

Figure 1.094: Opening's clearance

Figure 1.095: Grating or grill on the normal path of travel


Figure 1.096: Gratings or grills located to one side of pedestrian walkways

Figure 1.097: Adequate lighting over public walkways, steps and ramps

Figure 1.098 : Headroom clearance at passenger boarding zones

CHAPTER 3
PART 1 ACCESS TO BUILDING

Figure 2.001: Accessible entrances



Key

1. Wall partition or other obstruction
2. 300 mm clear (may be reduced if door is opened by remote automatic control)
3. Door hung from corner of room
4. Short return might enable the door to swing open beyond 90°
5. Doorset

Figure 2.002: Entrance Door Location and Side Clearance




Figure 2.003: Minimum clearance between guard and opened door




Figure 2.004: Colour Differentiated Door Frames




Figure 2.005: Clear width of doorways




Figure 2.006: Maneuvering clearances at manual swinging doors and gates




Figure 2.007: Maneuvering clearances at manual swinging doors and gates




Figure 2.008: Maneuvering clearances at doorways without doors, sliding doors, gates and folding doors





Figure 2.009: Maneuvering clearances at recessed doors and gates


Figure 2.010: Accessible Door Opening hardware

Figure 2.011: "D" type door or drawer handles




(a) Glazed or panelled doors with narrow stiles less than 100 mm wide

(b) Solid doors and doors with vision panels having side margins of 100 mm or more



(c) Plan section of cranked pull handle on a narrow style



(d) Vertical section showing a pull handle and horizontal pull rail

Key

1 Cranked pull handle, 19 mm to 35 mm diameter
2 Vertical pull handle, 19 mm to 35 mm diameter
3 Horizontal pull rail to help people close the door behind them
4 Lever handle
5 800 mm to 1 050 mm (900 mm preferred)
6 Bottom end of pull handle no lower than 700 mm and no higher than 1 050 mm above the floor
7 Top end of pull handle no lower than 1 300 mm above the floor
8 Fixing centres close to door edge
9 Doors with narrow stiles require cranked pull handles with an offset of not less than 50 mm from the door edge

NOTE 1 The lever handles and pull handles shown on this drawing will not necessarily be used on the same face of a door.

NOTE 2 Although the conventional "D" pull handle is shown in the figure, other patterns of pull handle are acceptable, provided they conform to the dimensional criteria.

Figure 2.012: pull handles for both external and internal doors and Location of the door opening and closing furniture (continued) (Dimension in millimetres)




Figure 2.013: Examples of lever furniture showing key dimensions (Dimensions in millimetres)

Figure 2.014: Partially glazed doors and limits of glazed panels




Figure 2.015: Minimum zone of visibility and examples of acceptable vision panel configurations (Dimension in millimetres)




Figure 2.016: Sliding cupboard door opening clearance

Figure 2.017: Occasional mats clearance with the floor surface



Figure 2.018: Interior thresholds limits




Figure 2.019: Interior door swing clearance




Figure 2.020: Space needed to allow access by people using crutches (Dimensions in millimetres)

Figure 2.021: Clearance for use of passageways and aisles by two persons one with mobility aid

Figure 2.022: Clearance and Turning Space for use of wheelchair in a public corridor

Figure 2.023: Clearance for use of mobility aids in corridors and hallways




Figure 2.024: Space allowances for corridors (Dimensions in millimetres)

Figure 2.025: Minimum Dimensional for Elevators Clear Space.




Figure 2.026: Platform lift doors and gates




Figure 2.027: Accessible Control Panel for Platform Lifts

Figure 2.028: Respective Dimensions of an elevator and platform for platform lifts to accommodate a stretcher.

Figure 2.029: Handrails and guard dimensions




Figure 2.030: Approach space for persons using mobility aids at drinking fountains




Figure 2.031: Table/Desk specifications for use by persons using mobility aids





Figure 2.032: Space dimensions in front of a work surface (Dimensions in millimetres)



Receptionist side

The dimensions allow a receptionist using a wheelchair with desk armrests to sit close to a counter at normal desk height

Visitor/customer side


The dimensions allow a visitor in a wheelchair to bring the arms of their wheelchair to the edge of the counter in order to read and sign a paper

NOTE Profiling the space below a counter will allow a number of structural support solutions.

Key

1 Upper writing surface for standing visitors/customers at 950 mm to 1 100 mm above the floor
2 Height of knee recess 700 mm min. above the floor
3 Counter top at 760 mm max. above the floor

Figure 2.033: Key heights of counters or reception desks (Dimensions in millimetres)




Key
1 Wheelchair turning space (1 500 x 1 500) mm
2 Effective clear width (see 6.4.3)

Figure 2.034: Minimum dimensions of an interview room (Dimensions in millimetres)

Figure 2.035: Vertical Limits for the mounting of storage or baggage lockers for persons with disabilities.

Figure 2.036: Lateral Limits for mounting of storage facilities.



Key

1 Reach range to the side for a standing person who has difficulty reaching and bending – 750 mm to 1 500 mm for frequent use and 700 mm to 1 625 mm for infrequent use


2 storage facilities or wall opposite

3 Reach range to the side from a wheelchair – 666 mm to 1 666 mm for frequent use and 666mm to 1 170 mm for infrequent use

4 sideways access

A1 Maximum shelf depth to allow reach to back of shelf from a sideways position when arm is horizontal.

Figure 2.037: Access to storage from the front when seated (Dimensions in millimetres)




Key

1 Lockers/filing cabinet
2 Line of obstruction (e.g. wall or storage)
3 Shelving
4 Mobile storage unit
5 Comfortable reach range above floor level – 450 mm for low shelf to 1 650 mm for high shelf (1 150 mm for high shelf when use is infrequent)
6 Clear space from obstruction to front of shelf where a knee space is provided
7 Clear space in front of cabinet where there is no knee space [A]

[A] Use of lower drawer will require access from side. Mobile storage units increase flexibility of use.

Figure 2.038: Access to shelves from the side (Dimensions in millimeters

Figure 2.039: Limits for mounting of mirrors over vanities and washbasins



a) In bathrooms and shower rooms

Location of independent washbasin, mirror and grab rails (not associated with a corner WC), for wheelchair users and ambulant disabled people


b) In a unisex accessible WC

Long mirror located away from washbasin suitable for wheelchair users and ambulant disabled people (mirror and associated fittings used within a unisex accessible WC compartment or within a separate-sex facility serving a range of compartments)

Key

1 Automatic hand dryer
2 Shaver point (where relevant)
3 600 mm vertical grab rail each side of mirror
4 Centre line of vertical grab rail
5 Mirror above basin, with base corresponding with top of washbasin
6 Tall mirror
A For ambulant disabled people only
B For both ambulant disabled people and wheelchair users

Figure 2.040: Location of independent mirrors, accessories and washbasins (Dimensions in millimetres)



Key

1 Clear space under worktop
2 150 mm deep sink bowl
3 Water heater (may be freestanding subject to safety requirements)
4 Floor unit
5 Microwave oven
6 Wheelchair turning space (1 500 × 1 500) mm
7 Refrigerator under worktop
8 Work surface 850 mm above floor level

Figure 2.041: Layout of shared refreshment facility (Dimensions in millimetres)

Figure 2.042: Limits for mounting of vending machine controls from the floor



Figure 2.043: Signage on vending machines produced in high contrast letters

---

Figure 2.044: Limits for mounting of controls for window blinds, drapes or louvres




Figure 2.045: Fire-alarm signals or elevator arrival call systems

Figure 2.046: Automatic detection systems – Wide zone (Side traffic)

Figure 2.047: Automatic detection systems – Narrow zone (Direct approaches or swing doors)




Figure 2.048: Text telephone with a digital display (TTY telephone)




Figure 2.049: Character Height





Figure 2.050: Braille measurement (measured centre-to-centre)

Figure 2.051: Controls and operating mechanisms

Figure 2.052: Limits for easy operation of controls



Key
1 Min. 350 mm from corner

Figure 2.053 Distance of outlets, switches and controls from the corner of a room

Figure 2.054: Audible signals for two-stage evacuation

Figure 2.055: FM Loop System




Figure 2.056: Height of telephone controls for wheelchair users (Dimensions in millimetres)

Figure 2.057: Easy to comprehend Pictograms



Figure 2.058: Exiting information in large print on a contrasting background

---

Figure 2.059: Large size print of lettering




Figure 2.060: Braille information located below room numbers



Figure 2.061: Changing/locker rooms signs

Figure 2.062: Design and mounting of ATM

Figure 2.063: Clearance for aisle spaces

Figure 2.064: Layout of a counter service

Figure 2.065: Plan view of cashier locations

Figure 2.066: Plan view of book stack area

Figure 2.067: Plan view of an entertainment or assembly area




Figure 2.068: Permitted Protrusions in Wheelchair Spaces




Figure 2.069: Wheelchair User turning space in a kitchenette

B 1488




Figure 2.070: Dimensional requirements of kitchenettes




Figure 2.071: Corridor Type kitchens




Figure 2.072: U-shaped kitchens





Figure 2.073: Bathrooms Dimension

Shower Rooms and Bathrooms



NOTE 1 Example shown is for right-hand transfer to shower seat and WC.


NOTE 2 For details of fittings associated with the shower, see Figure 50.

NOTE 3 The overall dimensions shown exclude such items as heat emitters and boxing in of pipework, and adjustments in room size will be needed to accommodate these items.

Key

1 Drop-down support rail
2 Shower curtain
3 Floor drain
4 Alarm pull cord
5 Vertical and horizontal grab rails
6 Tip-up shower seat
7 Optional tip-up seat for use when drying
8 Fall to floor drain no steeper than 1:50
9 Towel rail
10 Wheelchair turning space (1 500 × 1 500) mm
11 Horizontal pull rail to help close the door from a wheelchair
12 See Figure 45 for details of WC, basin and associated fittings

Figure 2.074: En-suite shower room with corner WC for independent use (Dimensions in millimetres)



NOTE 1 Example shown is for right-hand transfer to shower seat.


NOTE 2 For details of fittings associated with the shower, see Figure 50, and with the peninsular WC, see Figure 55.

NOTE 3 The overall dimensions shown exclude such items as heat emitters and boxing in of pipework, and adjustments in room size will be needed to accommodate these items.

Key

1 Peninsular WC with close-coupled cistern
2 Fall to floor drain no steeper than 1:50
3 Towel rail
4 Alarm pull cord
5 Vertical and horizontal grab rails
6 Full room cover tracked hoist system (or alternative system giving similar access to all sanitary fittings)
7 Shower curtain
8 Tip-up shower seat
9 Floor drain

Figure 2.075: En-suite shower room for use with a ceiling-mounted full room cover tracked hoist
system for assisted use (Dimensions in millimetres)



NOTE 1 Example shown is for left-hand transfer to bath.


NOTE 2 For details of accessories associated with the bath, see Figure 47 and with the peninsular WC, see Figure 55.

NOTE 3 The overall dimensions shown exclude such items as heat emitters and boxing in of pipework, and adjustments in room size will be needed to accommodate these items.

Key

1 Sliding doors
2 Alternative washbasin position
3 Vertical grab rails
4 Peninsular WC with close-coupled cistern
5 Alarm pull cord
6 Full room cover tracked hoist system (or alternative system giving similar access to all sanitary fittings)
7 Towel rail

Figure 2.076: En-suite bathroom with a ceiling-mounted full room cover tracked hoist system for assisted use (Dimensions in millimetres)




NOTE 1 Example shown is for right hand transfer to bath and WC.

NOTE 2 The overall dimensions shown exclude such items as heat emitters and boxing in of pipework, and adjustments in room size will be needed to accommodate these items.

Key

1 Horizontal pull rail to help close the door from a wheelchair
2 Two clothes hooks, one at 1 050 mm and the other at 1 400 mm above the floor
3 Sanitary dispenser
4 Disposal bin
5 Towel rail
6 Shelf
7 Bath transfer wall
8 Alarm pull cord
9 See Figure 52 for details of fittings on this wall
10 Vertical grab rails
11 Large washbasin with depth (front to back) no greater than 400 mm
12 Wheelchair turning space (1 500 x 1 500) mm
13 Sanitary disposal unit
14 Bath mixer tap
15 Drop-down support rail
16 Rail with padded back rest, where cistern is not close-coupled
17 Concealed cistern, 125 mm to 150 mm deep – width up to 400 mm, depending on location of cistern
18 Horizontal grab rail mounted on cranked wall

Figure 2.077: Bathroom for independent use incorporating a corner WC layout (Dimensions in millimetres)



NOTE 1 Example shown is for right-hand transfer to bath.

NOTE 2 The overall dimensions shown exclude such items as heat emitters and boxing in of pipework, and adjustments in room size will be needed to accommodate these items.

Key

1 Two clothes hooks, one at 1 050 mm and the other at 1 400 mm above the floor
2 Bath transfer seat
3 Towel rail
4 See Figure 53a) for details of fittings associated with this large washbasin
5 See Figure 47 for details of the bath and its associated grab rails
6 Wheelchair turning space (1 500 × 1 500) mm
7 Alarm pull cord
8 See Figure 55 for details of fittings associated with the peninsular WC

Figure 2.078: Bathroom for assisted use of a bath and peninsular WC (Dimensions in millimetres)





Figure 2.079: Grab rails where bath adjoins a wall, and transfer facilities (Dimensions in millimetres)




NOTE The overall dimensions shown exclude such items as heat emitters and boxing in of pipework, and adjustments in room size will be needed to accommodate these items.

Key

1 Shelf
2 Sanitary dispenser
3 Two clothes hooks, one at 1 050 mm and the other at 1 400 mm above the floor
4 Access, 700 mm wide, around peninsular bath for an assistant
5 Disposal bin
6 2 300 mm turning circle of mobile hoist
7 See Figure 53(a) for details of fittings associated with this range washbasin
8 Mixer tap
9 Alarm pull cord
10 Towel rail
11 See Figure 55 for details of peninsular WC and associated fittings
12 Extra space for an assistant to help on other side of peninsular bath

Figure 2.080: Bathroom allowing assisted use of the bath (and WC) using a mobile hoist operated by an assistant (Dimensions in millimetres)




Key

1 Paper towel dispenser
2 Full length mirror
3 Large sanitary disposal bin, if possible recessed into the wall
4 Alarm reset button
5 Full room cover tracked hoist system
6 Vertical grab rail
7 Drop-down support rails, one with a toilet roll holder
8 Flat-topped close-coupled cistern providing a back rest and a colostomy changing surface for standing users (where high or low level cisterns are used, a rail with a padded back rest and a separate colostomy changing shelf 125 mm to 150 mm deep and preferably 400 mm wide, with its surface 950 mm above floor level, should be provided)
9 Peninsular WC (see Figure 55 for the location of associated fittings)
10 Large power-assisted height-adjustable washbasin
11 Waste disposal bin
12 Manually-operated hand dryer
13 Retractable privacy curtain/screen
14 Alarm pull cord
15 Height-adjustable showering/changing bench, min. 1 800 mm long
16 Floor drain
17 Shower unit
18 Wide paper roll dispenser for use on the changing bench
19 Sanitary towel dispenser
20 Two clothes hooks, one at 1 050 mm and the other at 1 400 mm above the floor

NOTE Details of common features of sanitary accommodation are described in 12.2 and accessories related to toilets in 12.6.6. Advice on particular products is available from the Changing Places Consortium (see Bibliography under Information sources).

Figure 2.081: Example of fittings and accessories in a Changing Places facility



NOTE The example shown is for right hand transfer to the shower seat and WC.

Key

1 Television
2 Refrigerator
3 Luggage rack
4 Drawer unit and clear space under
5 800 mm min. unobstructed knee recess in wardrobe, with no plinth
6 Effective clear width (see Table 2)
7 See Figure 42 for details of a shower room with corner WC for independent use, Figure 44 for details of a bathroom with a tracked hoist system and Figure 46 for details of a bathroom with a peninsular WC for assisted use
A (1 500 × 1 500) mm min. allows front facing or 45° oblique transfer by wheelchair user
B (2 250 × 2 100) mm min. allows transfer methods used in A and also space for a mobile hoist to be turned through 180°
C 700 mm min. allows an assistant to help with the transfer from the other side of a bed

Figure 2.082: Accessible bedroom with en-suite sanitary facilities (Dimensions in millimetres)




Figure 2.083: Accessible bed layouts (Dimensions in millimetres)

B 1500




Figure 2.084: Wheelchair access to balconies (Dimensions in millimetres)






Figure 2.085: Circulation Space for Persons using Wheelchairs or Scooters in the Master Bedroom



Key

1 Steps
2 Aisle
3 (1 400 × 900) mm nominal wheelchair spaces
4 More seats can be removed if necessary to create more wheelchair spaces
5 Rear wall

Figure 2.086: Location of wheelchair spaces in front of a rear aisle (Dimensions in millimetres)



Key
1 Rostrum
2 The rostrum as well as seats on the rostrum and seats in the next row can be removed to create more wheelchair spaces
3 (1 400 × 900) mm nominal wheelchair spaces
4 Rear wall
5 Aisle
6 Steps

Figure 2.087: Location of wheelchair spaces at a seat way (Dimensions in millimetres)




Figure 2.088: Tactile warning surface




Figure 2.089: level loop pile of non-static nylon with a pile height




Figure 2.090: Fire suppression systems



Figure 2.091: Escape route symbols




Figure 2.092: Safe holding areas



Figure 2.093: Limit of obstruction



Figure 2.094: Office equipment located to one side of the normal path of travel

Figure 2.095: Cane Detectable Office Equipment



Figure 2.096: Cane detectable temporary barriers and hoardings

Table 1.1: Limits for Ramp Gradients

Going of a Flight	Maximum Gradient	Maximum Rise
10	1:20	500
9	1:19	473
8	1:18	444
7	1:17	411
6	1:16	375
5	1:15	333
4	1:14	285
3	1:13	230
Not exceeding 2	1:12	166

Table 1.2: Maximum slope and length of ramps

Max. rise, mm	Max. slope	Max. slope, mm/m	Max. length between landings, mm	Outdoor use	Indoor use
no limit	Less than 1 in 20 (5,0 %)	<50	no limit	yes	yes
900	1 in 20 (5,0 %)	50	10 000	yes	yes
460	1 in 19 (5,3 %)	53	8 740	yes	yes
420	1 in 18 (5,6 %)	56	7 560	yes	yes
385	1 in 17 (5,9 %)	59	6 545	yes	yes
350	1 in 16 (6,3 %)	63	5 600	yes	yes
315	1 in 15 (6,7 %)	67	4 725	yes	yes
280	1 in 14 (7,1 %)	71	3 920	yes	yes
245	1 in 13 (7,7 %)	77	3 185	yes	yes
210	1 in 12 (8,3 %)	83	2 520	yes	yes
180	1 in 11 (9,1 %)	91	1 980	curb ramps only	not recommended
150	1 in 10 (10,0 %)	100	1 500	curb ramps only	not recommended
110	1 in 9 (11,1 %)	111	990	curb ramps only	not recommended
75	1 in 8 (12,5 %)	125	600	curb ramps only	Threshold ramps only

Table 1.3: Number of Spaces in Entertainment Buildings Designated

Seating Capacity	Provision of Spaces for Wheelchairs	
	Permanent	Removable
Up to 600	3% of full seating capacity	Remainder to make a total of 18
Over 600 but less than 10,000	3% of full seating capacity	Additional provision, if desired
NOTE: Percentages need to be rounded up to determine the recommended number of spaces. For seating capacities of 10,000 or more.		

Table 1.4: Manoeuvring Clearances at Manual Swinging Doors and Gates

Type of Use		Minimum Maneuvering Clearance	
Approach Direction	Door or Gate Side	Perpendicular to Doorway	Parallel to Doorway (beyond latch side unless noted)
From front	Pull	60 inches (1525 mm)	18 inches (455 mm)
From front	Push	48 inches (1220 mm)	0 inches (0 mm)[1]
From hinge side	Pull	60 inches (1525 mm)	36 inches (915 mm)
From hinge side	Pull	54 inches (1370 mm)	42 inches (1065 mm)
From hinge side	Push	42 inches (1065 mm)[2]	22 inches (560 mm)[3]
From latch side	Pull	48 inches (1220 mm)[4]	24 inches (610 mm)
From latch side	Push	42 inches (1065 mm)[4]	24 inches (610 mm)

1. Add 12 inches (305 mm) if closer and latch are provided.
2. Add 6 inches (150 mm) if closer and latch are provided.
3. Beyond hinge side.
4. Add 6 inches (150 mm) if closer is provided.

Table 1.5: Manoeuvring Clearances at Doorways without Doors or Gates, Manual Sliding Doors and manual Doors

	Minimum Maneuvering Clearance	
Approach Direction	Perpendicular to Doorway	Parallel to Doorway (beyond stop/latch side unless noted)
From Front	48 inches (1220 mm)	0 inches (0 mm)
From side[1]	42 inches (1065 mm)	0 inches (0 mm)
From pocket/hinge side	42 inches (1065 mm)	22 inches (560 mm)[2]
From stop/latch side	42 inches (1065 mm)	24 inches (610 mm)

1. Doorway with no door only.
2. Beyond pocket/hinge side.

Table 2.1: Manoeuvring Clearances at Manual Swinging Doors and Gates

B 1508

Type of Use		Minimum Maneuvering Clearance	
Approach Direction	Door or Gate Side	Perpendicular to Doorway	Parallel to Doorway (beyond latch side unless noted)
From front	Pull	60 inches (1525 mm)	18 inches (455 mm)
From front	Push	48 inches (1220 mm)	0 inches (0 mm)[1]
From hinge side	Pull	60 inches (1525 mm)	36 inches (915 mm)
From hinge side	Pull	54 inches (1370 mm)	42 inches (1065 mm)
From hinge side	Push	42 inches (1065 mm)[2]	22 inches (560 mm)[3]
From latch side	Pull	48 inches (1220 mm)[4]	24 inches (610 mm)
From latch side	Push	42 inches (1065 mm)[4]	24 inches (610 mm)

1. Add 12 inches (305 mm) if closer and latch are provided.
2. Add 6 inches (150 mm) if closer and latch are provided.
3. Beyond hinge side.
4. Add 6 inches (150 mm) if closer is provided.

Table 2.2: Maneuvering Clearances at Doorways without Doors or Gates, Manual Sliding Doors and Manual Folding Doors




Table 2.3: Children Reach Ranges

Reach	Ages 3 and 4	Ages 5 to 8	Ages 9 to 12
Maximum	915mm	1015mm	1120mm
Minimum	510mm	455mm	405mm

Table 2.4: Effective Clear Widths of Doors

B 1510

Direction of approach of wheelchair	Minimum effective clear width of door leaf (mm)	
	New buildings	Existing buildings
Straight-on (without a turn or oblique approach)	800	750
At right angles from an access route at least 1 500 mm wide	800	750
At right angles from an access route at least 1 200 mm wide	825	775
At right angles from an access route at least 900 mm wide	N/A	800
External doors and internal lobby doors at the entrance of buildings used by the general public	1 000	775 [A]

NOTE 1 An effective clear width of less than 800 mm might result in people with poor manoeuvring ability or with large wheelchairs not being able to pass through without damage to themselves or the door or frame. Use of the 1 000 mm effective clear width more easily accommodates people with assistance dogs and where there is heavy pedestrian traffic. For buildings used by the general public, the greater effective clear width is likely to be best achieved using power-assisted doors.

NOTE 2 For new buildings, effective clear widths of 800 mm and 825 mm are achievable using a 926 mm door leaf, provided the door opens beyond 90° and the projection of door furniture does not reduce the effective clear width.

NOTE 3 Sports facilities have their own requirements for the effective width of doors, e.g. tennis sports wheelchairs require a doorway with an effective clear width of 1 000 mm for convenient access (see Accessible sports facilities (711)).

[A] Where the entire frontage is being replaced, the width for a new building should be used.

Table 2.5: Braille Dimensions

Measurement Range	Minimum to Maximum
Dot base diameter	1.5mm to 1.6mm
Distance between two dots in the same cell	2.3mm to 2.5mm
Distance between corresponding dots in adjacent cells	6.1mm to 7.6mm
Dot height	0.6mm to 0.9mm
Distance between corresponding dots from one cell directly below	10.0mm to 10.2mm

Table 2.6: Receivers for Assistive Listening Systems

Capacity of Seating in Assembly Area	Minimum Number of Required Receivers	Minimum Number of Required Receivers Required to be Hearing-Aid Compatible
50 or below	2	2
51 to 200	2 plus 1 per 25 seats over 50 seats[1]	2
201 to 500	2 plus 1 per 25 seats over 50 seats[1]	1 per 4 Receivers[1]
501 to1000	2 plus 1 per 25 seats over 50 seats[1]	1 per 4 Receivers[1]
1001 to 2000	2 plus 1 per 25 seats over 50 seats[1]	1 per 4 Receivers[1]
2001 and above	2 plus 1 per 25 seats over 50 seats[1]	1 per 4 Receivers[1]

Note: [1] or fraction thereof

Table 2.7 Guestrooms with Mobility Features

Total Number of Guestrooms Provided	**Minimum Number of Required Rooms Without Roll-in Showers**	**Minimum Number of Required Rooms With Roll-in Showers**	**Total Number of Required Rooms**
1 to 25	1	0	1
26 to 50	2	0	2
51 to 75	3	1	4
76 to 100	4	1	5
101 to 150	5	2	7
151 to 200	6	2	8
201 to 300	7	3	10
301 to 400	8	4	12
401 to 500	9	4	13
501 to 1000	2 percent of total	1 percent of total	3 percent to total
1001 and over	20, plus 1 for each 100, or fraction thereof, over 1000	10, plus 1 for each 100, or fraction thereof, over 100	30, plus 2 for each 100, or fraction thereof, over 1000

B 1512

Table 2.8 Guestrooms with Communication Features

Total Number of Guestrooms Provided	Minimum Number of Required Guestrooms with Communication Features
2 to 25	2
26 to 50	4
51 to 75	7
76 to 100	9
101 to 150	12
151 to 200	14
201 to 300	17
301 to 400	20
401 to 500	22
501 to 1000	5 percent of total
1001 and over	50, plus 3 for each 100 over 1000

SECOND SCHEDULE

SYMBOLS AND ABBREVIATIONS

^{O}C	Degree Celsius
^{O}F	Degree Fahrenheit
^{O}K	Degree Kelvin
%	*per cent*
ATM	Automated Teller Machine
BS	British Standard
CD	Compact Disc
CSO	Civil Society Organisation
FM	Frequency Modulation
ft.	Feet
HVAC	Heating Ventilation and Air Conditioning
Mm	Millimetre
NBC	National Building Code
N-m	Newton meter
OPDs	Organisations of Persons with Disabilities
PSD	Posttraumatic Stress Disorder
PTV	Pendulum Test Value
PXO	Pedestrian Crossover
SMS	Short Messaging Service
SRV	Slip Resistance Value
TTY	Teletypewriter

DONE at Abuja this 22nd day of May, 2023

AMINA RAHMA AUDU
Acting Chairman Governing Council
National Commission for Persons with Disabilities

EXPLANATORY NOTE
(*This note does not form part of these Regulations, but is intended to explain its purports*)

These Regulations provides guidelines to ensure effective collaboration with relevant agencies in ensuring easy and unimpeded access to services in the Nigerian built environment by persons with disabilities; provide specifications for policy makers, regulators, implementers, and service providers to ensure quality and non-discriminatory services in the Nigerian built environment; provide standards and codes for the design and construction of an accessible built environment, including roads, and transportation facilities; provide a tool for measurement or auditing of universal accessibility in the built environment; guide developers, designers and other persons involved in the built environment process in incorporating accessibility principles in the planning, design, and execution stages of building work; and increase awareness on accessibility standards and the need for a barrier-free design in the built environment.